

LOCATION OF WATER WELL		Fraction	Near Center	Section Number	Township Number		Range Number
County: Barton		1/4	1/4 NW 1/4	23	T	20 S	R 14 E/W
Distance and direction from nearest town or city? 4 miles south and 1 3/4 miles west of Great Bend, KS				Street address of well if located within city?			
WATER WELL OWNER: Marvin Johnston				Board of Agriculture, Division of Water Resources			
R#, St. Address, Box #: P.O. 139				Application Number: Not Available			
City, State, ZIP Code: Great Bend, KS 67530							
DEPTH OF COMPLETED WELL: 132 ft. Bore Hole Diameter: 24 in. to 132 ft. and in. to ft.							
Well Water to be used as:							
1 Domestic		3 Feedlot		6 Oil field water supply		9 Dewatering	
2 Irrigation		4 Industrial		7 Lawn and garden only		10 Observation well	
Well's static water level: 10 1/2 ft. below land surface measured on 12 month 30 day 1980 year							
Pump Test Data: Well water was ft. after hours pumping gpm							
St. Yield Not ck'd gpm: Well water was ft. after hours pumping gpm							
TYPE OF BLANK CASING USED:							
1 Steel		3 RMP (SR)		6 Asbestos-Cement		9 Other (specify below)	
2 PVC		4 ABS		7 Fiberglass		10 Asbestos-cement	
Blank casing dia: 16 in. to 32 ft. Dia: 16 in. to 112 ft. Dia: in. to ft.							
Casing height above land surface: 12 in., weight 31.75 lbs./ft. Wall thickness or gauge No. 188							
TYPE OF SCREEN OR PERFORATION MATERIAL:							
1 Steel		3 Stainless steel		5 Fiberglass		8 RMP (SR)	
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS	
Screen or Perforation Openings Are:							
1 Continuous slot		3 Mill slot		6 Wire wrapped		9 Drilled holes	
2 Louvered shutter		4 Key punched		7 Torch cut		10 Other (specify) Doerr Bridge Slot	
Screen-Perforation Dia: 16 in. to 72 ft. Dia: 16 in. to 132 ft. Dia: in. to ft.							
Screen-Perforated Intervals: From 32 ft. to 72 ft. From ft. to ft.							
Travel Pack Intervals: From 112 ft. to 132 ft. From ft. to ft.							
GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other							
Grouted Intervals: From 0 ft. to 10 ft. From ft. to ft.							
What is the nearest source of possible contamination:							
1 Septic tank		4 Cess pool		7 Sewage lagoon		10 Fuel storage	
2 Sewer lines		5 Seepage pit		8 Feed yard		11 Fertilizer storage	
3 Lateral lines		6 Pit privy		9 Livestock pens		12 Insecticide storage	
Direction from well: n/a How many feet: n/a? Water Well Disinfected? Yes No X							
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, date sample							
Submitted month day year: Pump Installed? Yes 3-30-81 No							
Yes: Pump Manufacturer's name: Peerless Pump Co. Model No. 12LD-2 HP 50 Volts 460							
Depth of Pump Intake: 60 ft. Pumps Capacity rated at 1000 gal./min.							
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other							
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was							
Completed on 12 month 30 day 1980 year							
And this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185							
This Water Well Record was completed on 4 month 2 day 1981 year under the business							
Name of Clarke Well & Eq., Inc. by (signature)							
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM TO		LITHOLOGIC LOG		FROM TO	
		0 5		Topsoil		88 105	
		5 50		Sand & gravel, sandy clay		105 114	
		50 58		Med-coarse sand & gravel		114 122	
		58 63		Light gray clay		122 125	
		63 68		Sandy tan clay & v.fine sand & gravel		125 132	
		68 75		Sand & grvl, sandy clay			
		75 85		Brown clay, sandy, strks cemented sand			
		85 88		Fine sand & gravel w/strk sandy clay, cmted sand			
ELEVATION: Unknown							
Depth(s) Groundwater Encountered 1. 10 ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)							
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.							

OFFICE USE ONLY

T

20

R

14

E

SEC.

23

of 14

1/4