

LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number
County: BARTON		SE 1/4 SE 1/4 NE 1/4	32	T 20 S	R 14 NW
Distance and direction from nearest town or city? Approx. 5 1/2 south and 4 west of Great Bend, KS		Street address of well if located within city?			
WATER WELL OWNER: Jim Romine		Board of Agriculture, Division of Water Resources			
R#, St. Address, Box #: Route 1		Application Number: Not Required			
City, State, ZIP Code: Great Bend, KS 67530					
DEPTH OF COMPLETED WELL: 74 ft. Bore Hole Diameter: 9 in. to 74 ft., and 74 in. to 74 ft.					
Well Water to be used as:		5 Public water supply 8 Air conditioning 11 Injection well			
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)					
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well					
Well's static water level: 23 ft. below land surface measured on 10 month 31 day 1979 year					
Pump Test Data: Well water was 10 ft. after 31 hours pumping gpm					
St. Yield Not Check'd gpm: Well water was 10 ft. after 31 hours pumping gpm					
TYPE OF BLANK CASING USED:		Casing Joints: Glued Clamped Welded solvent weld			
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Styrene 200					
2 PVC 4 ABS 7 Fiberglass					
Blank casing dia: 5 in. to 64 ft., Dia 5 in. to 64 ft., Dia 5 in. to 64 ft., Dia 5 in. to 64 ft.					
Casing height above land surface: 12 in., weight 1.5 lbs./ft. Wall thickness or gauge No. 200					
TYPE OF SCREEN OR PERFORATION MATERIAL:		10 Asbestos-cement 11 Other (specify) Styrene 200			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 12 None used (open hole)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS					
Screen or Perforation Openings Are:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
Screen-Perforation Dia: 5 in. to 74 ft., Dia 5 in. to 74 ft., Dia 5 in. to 74 ft., Dia 5 in. to 74 ft.					
Screen-Perforated Intervals: From 64 ft. to 74 ft., From 64 ft. to 74 ft., From 64 ft. to 74 ft., From 64 ft. to 74 ft.					
Travel Pack Intervals: From 55 ft. to 74 ft., From 55 ft. to 74 ft., From 55 ft. to 74 ft., From 55 ft. to 74 ft.					
GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other			
Grouted Intervals: From 0 ft. to 10 ft., From 35 ft. to 55 ft., From 35 ft. to 55 ft., From 35 ft. to 55 ft.					
What is the nearest source of possible contamination:		10 Fuel storage-Above grd 44 Abandoned water well			
1 Septic tank 4 Cess pool 7 Sewage lagoon 11 Fertilizer storage 15 Oil well/Gas well					
2 Sewer lines 5 Seepage pit 8 Feed yard 12 Insecticide storage 16 Other (specify below)					
3 Lateral lines 6 Pit privy 9 Livestock pens 13 Watertight sewer lines					
Direction from well: Southeast How many feet 20 ? Water Well Disinfected? Yes XX No					
Has a chemical/bacteriological sample submitted to Department? Yes NoXX If yes, date sample					
Has submitted month day year Pump Installed? Yes XX No					
Yes: Pump Manufacturer's name Berkeley Pump Co. Model No. 4BL-15 HP 1 Volts 230					
Depth of Pump Intake 42 ft. Pumps Capacity rated at 15 gal./min.					
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other					
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was					
Completed on 10 month 31 day 1979 year					
And this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185					
This Water Well Record was completed on 11 month 13 day 1979 year under the business					
Name of CLARKE WELL & EQUIPMENT, INC. by (signature) <i>D. W. Clarke</i>					
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG	
		0 10 Topsoil & brown clay			
		10 47 Sand & gravel			
		47 62 Sandy tan clay			
		62 74 Sand & gravel			
		OLD WELL APPROXIMATELY 60' EAST WAS CONTAMINATED FROM SEPTIC TANK CASING HAD RUSTED OUT. WELL WAS CALIBRATED & PLUGGED TO 70' BOTTOM - DEPTH APPROX. 50'			
ELEVATION: UNKNOWN					
Depth(s) Groundwater Encountered 1. 23 ft. 2. 23 ft. 3. 23 ft. 4. 23 ft.		(Use a second sheet if needed)			
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

20

ft.

ft.

R

14

ft.

ft.

ft.

SEC.

32

day

SE 1/4

SE 1/4

NE 1/4

ft.

ft.

ft.

ft.