

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction 1/4 SE 1/4 NE 1/4	Section number 34	Township number T 14 S R 20 E/W	Range number
2. Distance and direction from nearest town or city: 4 E 4 W 3 1/2 S of Great Bend			3. Owner of well: Texaco Inc R.R. or street: City, state, zip code: Great Bend, Ks.			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 10 in. Completion date _____ Well depth 65 ft. 9-24-76		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☒ Oil field water ☐ Other		
5. Type and color of material		From	To	9. Casing: Material pvc Height: Above or below Threaded ☐ Welded ☒ Surface 18 in. RMP ☐ PVC pvc Weight _____ lbs./ft. Dia. 4 in. to 65 ft. depth Wall thickness: _____ inches or Dia. _____ in. to _____ ft. depth Gauge No. 1/4		
Sandy Top Soil		0	1	10. Screen: Manufacturer's name R/B Type pvc 1/16 Dia. 4 Slot/gauze _____ Length 20 Set between 45 ft. and 65 ft. _____ ft. and _____ ft. Gravel pack? ☒ Size range of material 1/2 3/4 3/8		
Sandy Clay		1	10	11. Static water level: _____ mo./day/yr. 9 ft. below land surface Date 9-24-76		
Sand		10	18	12. Pumping level below land surfaces: 15 ft. after 1 hrs. pumping 75 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 200 g.p.m.		
Clay		18	19	13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____		
Good Sand Gravel		19	37	14. Well head completion: ☐ Pitless adapter 18 inches above grade		
Clay		37	39	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Sand Gravel Little Clay		39	50	16. Nearest source of possible contamination: 300 ft. South Direction oil well Well disinfected upon completion? Yes ☐ No ☐		
Good Clean Sand Gravel		50	65	17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name Great Bend, Ks. License No. _____ Address _____ Signed Media Dodson Date 10/29/76 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		1906				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5