


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Barton	SW 1/4 SW 1/4 NE 1/4	36	T 20 S	R 14 EW

Distance and direction from nearest town or city street address of well if located within city?

Approximately 5 miles south and 1 3/4 east of Great Bend, KS

2 WATER WELL OWNER:	Kansas Corporation Commission	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	2301 E. 13	Application Number: N/A
City, State, ZIP Code :	Hays, KS 67601	

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 64 ft. ELEVATION: unknown
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL . . . 21 . . . ft. below land surface measured on mo/day/yr
	Pump test data: Well water was not ch'd. ft. after hours pumping gpm
	Est. Yield unknown gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter . . . 5 . . . in. to . . . 64 . . . ft., and in. to ft.
	WELL WATER TO BE USED AS:
	5 Public water supply 8 Air conditioning 11 Injection well
	1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
	2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
	Was a chemical/bacteriological sample submitted to Department? Yes No x; If yes, mo/day/yr sample was submitted
	Water Well Disinfected? Yes No x

3 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued . . . x . . . Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter 2 . . . in. to . . . 57 . . . ft., Dia in. to ft., Dia in. to ft.			
Casing height above land surface 24 in., weight 44 lbs./ft. Wall thickness or gauge No. 091			

TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement
1 Steel	3 Stainless steel	5 Fiberglass
2 Brass	4 Galvanized steel	6 Concrete tile
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut
1 Continuous slot	3 Mill slot	6 Wire wrapped
2 Louvered shutter	4 Key punched	7 Torch cut
		8 RMP (SR)
		9 ABS
		10 Other (specify)
		11 None used (open hole)
		12 None used (open hole)

SCREEN-PERFORATED INTERVALS:	From 57 ft. to 62 ft., From ft. to ft.
	From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 62 ft., From ft. to ft.
	From ft. to ft., From ft. to ft.

5 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other . Bentonite hole plug
Grout Intervals: From ft. to ft., From ft. to ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:	5 Livestock pens	14 Abandoned water well		
1 Septic tank	4 Lateral lines	7 Pit privy		
2 Sewer lines	5 Cess pool	8 Sewage lagoon		
3 Watertight sewer lines	6 Seepage pit	9 Feedyard		
		10 Fuel storage		
		11 Fertilizer storage		
		12 Insecticide storage		
		13 Old plugged oil well		
		15 Oil well/Gas well		
		16 Other (specify below)		

Direction from well? south	How many feet? 70				
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	Fine sand, Topsoil			
4	12	Clay, tan			
12	14	Fine Sand			
14	18	Clay, brown, sandy, soft			
18	45	Sand and Gravel, very fine and fine sand with thin yellow clay streak at 42'			
45	55	Sand and Gravel, fine to very fine with thin yellow clay streak at 48'			
55	62	Sand and Gravel, fine to very fine to medium, silty			
62	64	Clay Brown, soft			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-16-89 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . . 185 This Water Well Record was completed on (mo/day/yr) 8-24-89 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>
--

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320. Telephone: 913-296-5514. Send one to WATER WELL OWNER and retain one for your records.