

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Barton		SW 1/4 SW 1/4 SW 1/4	2	T 20 S	R 14 E W
Distance and direction from nearest town or city street address of well if located within city?					
At 397 Grove Terr., Great Bend					
2 WATER WELL OWNER:		Dick Meitler			
RR#, St. Address, Box #		Box 1205			
City, State, ZIP Code		Great Bend, KS 67530			
		Board of Agriculture, Division of Water Resources			
		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 66.5 ft.		ELEVATION: unknown	
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 9.5 ft. below land surface measured on mo/day/yr 11-19-94			
		Pump test data: Well water was not ch'd ft. after hours pumping gpm			
		Est. Yield unknown gpm Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 9 in. to 65 ft. and in to ft.			
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes No X		If yes, mo/day/yr sample was submitted			
5 TYPE OF BLANK CASING USED:		Water Well Disinfected? Yes X No			
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile CASING JOINTS Glued X Clamped			
2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below) Welded			
Blank casing diameter 5 in. to 53 ft. Dia.		7 Fiberglass Threaded			
Casing height above land surface 18 in. weight 2.36 lbs. ft. Wall thickness or gauge No. .214					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass		8 RMP (SR)			
2 Brass 4 Galvanized steel 6 Concrete tile		9 ABS 11 Other (specify)			
SCREEN OR PERFORATION OPENINGS ARE:		12 None used (open hole)			
1 Continuous slot 3 Mill slot 5 Gauzed wrapped		8 Saw cut 11 None (open hole)			
2 Louvered shutter 4 Key punched 6 Wire wrapped		9 Drilled holes			
SCREEN-PERFORATED INTERVALS: From 53 ft. to 65 ft.		10 Other (specify)			
GRAVEL PACK INTERVALS: From 25 ft. to 35 ft.					
From 45 ft. to 65 ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other		Bentonite holeplug			
Grout Intervals: From 0 ft. to 25 ft.		From 35 ft. to 45 ft.			
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy		11 Fuel storage 15 Oil well/Gas well			
2 Sewer lines 5 Cess pool 8 Sewage lagoon		12 Fertilizer storage 16 Other (specify below)			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		13 Insecticide storage House			
Direction from well? west		How many feet? 14			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5.5	Topsoil			
5.5	7	Sand, fine to medium			
7	25	Gravel, very coarse and clean			
25	48	Clay, tan			
48	65	Sand and gravel, medium to coarse, clean, loose			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11-19-94 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 185		This Water Well Record was completed on (mo/day/yr) 11-28-94			
under the business name of Clarke Well & Equipment, Inc.		by (signature) <i>Clarke Well & Equipment</i>			

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRINT CLEARLY and legibly. Please do not blank, underline or circle the correct answers. Send two true copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66606-0001. Telephone: (313) 296-5541. Send one to WATER WELL OWNER and retain one for your record.