


WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County McPherson	Township name Lonetree	Fraction SE 1/4 - SE 1/4	Section number 7	Town number T-20-S	Range number R-2-W																																													
Distance and direction from nearest town or city: 23 1/2 miles East - 2 North ELYRIA, KANS				3 Owner of well: RAY RATSLOFF Address: RR -1 McPherson																																															
Locate with "X" in section below: N  W S 1 Mile		Sketch map:		4 Well depth: 78 ft. Date of completion 5/7/75 Well diameter 6" in. 14" bore																																															
2 Type and color of material				5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																																															
				6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐																																															
				7 Casing: Material PVC Height: above/below Threaded ☐ Welded ☒ Surface 24 in. Diam. 6" Weight 3.22 lbs./ft. + 24 in. to 80' ft. depth Drive shoe? ☐ Yes ☒ No _____ in. to _____ ft. depth																																															
				8 Screen: Manufacturer own - pipe Mon. Type PVC Dia. 6" Slot/gauze 10/68 Length 15 Set between 50 ft. and 65 ft. Fittings: 1/8" to 3/8" Gravel pack ☐ Yes ☐ No Size range of material _____																																															
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:60%;">Type and color of material</th> <th style="width:10%;">From</th> <th style="width:10%;">To</th> </tr> </thead> <tbody> <tr><td>Loam</td><td>0</td><td>5</td></tr> <tr><td>" to red clay</td><td>5</td><td>10</td></tr> <tr><td>hard red clay</td><td>10</td><td>15</td></tr> <tr><td>Sandy clay</td><td>15</td><td>19</td></tr> <tr><td>Sand brown - hard size</td><td>19</td><td>24</td></tr> <tr><td>grey red clay</td><td>24</td><td>25</td></tr> <tr><td>light grey - brown clay</td><td>25</td><td>45</td></tr> <tr><td>SANDY clay - brown</td><td>45</td><td>50</td></tr> <tr><td>SAND med size (1/4" clay lvs)</td><td>50</td><td>57</td></tr> <tr><td>Limestone rock layered</td><td>57</td><td>59</td></tr> <tr><td>grey clay - sand - layered</td><td>59</td><td>62</td></tr> <tr><td>sand & thin layers of lime</td><td>62</td><td>65</td></tr> <tr><td>stone rock</td><td>65</td><td>78</td></tr> <tr><td>grey clay</td><td></td><td></td></tr> </tbody> </table>				Type and color of material	From	To	Loam	0	5	" to red clay	5	10	hard red clay	10	15	Sandy clay	15	19	Sand brown - hard size	19	24	grey red clay	24	25	light grey - brown clay	25	45	SANDY clay - brown	45	50	SAND med size (1/4" clay lvs)	50	57	Limestone rock layered	57	59	grey clay - sand - layered	59	62	sand & thin layers of lime	62	65	stone rock	65	78	grey clay			9 Static water level: 30 ft. below land surface Date 5/7/75		
				Type and color of material	From	To																																													
				Loam	0	5																																													
				" to red clay	5	10																																													
				hard red clay	10	15																																													
				Sandy clay	15	19																																													
				Sand brown - hard size	19	24																																													
				grey red clay	24	25																																													
				light grey - brown clay	25	45																																													
				SANDY clay - brown	45	50																																													
SAND med size (1/4" clay lvs)	50	57																																																	
Limestone rock layered	57	59																																																	
grey clay - sand - layered	59	62																																																	
sand & thin layers of lime	62	65																																																	
stone rock	65	78																																																	
grey clay																																																			
10 Pumping level below land surfaces: 50 ft. after 2 hrs. pumping 15 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 20 g.p.m.																																																			
11 Water sample submitted: ANALY run - results avail ☐ Yes ☒ No Date _____																																																			
12 Well head completion: ☒ Pitless adapter 24" inches above grade																																																			
13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 20 ft. to 3 ft.																																																			
14 Nearest source of possible contamination: ft. 75 Direction North Type corn Well disinfected upon completion? ☒ Yes ☐ No																																																			
15 Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																																			
16 Remarks: elevation				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PAUL'S INC 175 Business name License No. Address Box 26, Hesston Signed Paul B. Smith Date 5/8/75 Authorized representative																																															