

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: McPherson		SE 1/4 NE 1/4 NE 1/4	17	T 20 S	R 2 E (W)
Distance and direction from nearest town or city street address of well if located within city? 6 North - 2 West - 2 North of Moundridge					
2 WATER WELL OWNER: Dwight Goering					
RR#, St. Address, Box # : RR #5			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Moundridge KS 67107			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 67 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 44 ft. 2. 20 ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL 17 ft. below land surface measured on mo/day/yr 10-29-84			
		Pump test data: Well water was 68 ft. after 2 hours pumping 4 gpm			
		Est. Yield 4 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 11 in. to 67 ft. and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No X ; If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes X No _____			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped _____ 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass Threaded _____					
Blank casing diameter 5 in. to 20 ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.					
Casing height above land surface 18 in. weight 2.37 lbs./ft. Wall thickness or gauge No. 2.14					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) _____ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped factory 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From 20 ft. to 30 ft. From 45 ft. to 55 ft.					
GRAVEL PACK INTERVALS: From 10 ft. to 67 ft. From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____					
Grout Intervals: From 0 ft. to 10 ft. From _____ ft. to _____ ft. From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ 13 Insecticide storage					
Direction from well? North		How many feet? 75'			
FROM	TO	LITHOLOGIC LOG		FROM	TO
0	5	Leam to br clay			
5	15	brown clay			
15	20	sandy light br clay			
20	29	sand fine w/ clay seams			
29	44	light brown clay w/ sand seams			
44	60	sand medium			
60	67	green red shale to dark wettington shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-29-84 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 457 This Water Well Record was completed on (mo/day/yr) 12-1-84 under the business name of UNITED WATER WELL & PUMP by (signature) Paul Burchett					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					