

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <i>McPherson</i>	Fraction <i>SW 1/4 SW 1/4 SW 1/4</i>	Section number <i>25</i>	Township number <i>T 20 S</i>	Range number <i>R 2 E</i>
2. Distance and direction from nearest town or city: <i>5 N - 1 E - 1/4 N</i>		3. Owner of well: <i>Don. W. Johnson</i> R.R. or street: <i>R.R.</i> City, state, zip code: <i>Salina, Kans. 67443</i>				
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: <i>House</i> <i>Drainage</i> <i>Well</i> <i>300'</i> <i>100'</i> <i>30'</i> <i>CCA</i> <i>Barn</i> <i>Hay</i>				
5. Type and color of material		From	To	6. Bore hole dia. <i>8"</i> in. Completion date <i>10-23-75</i> Well depth <i>36</i> ft.		
<i>Top Soil</i>		<i>0</i>	<i>1</i>	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
<i>Gray clays & fine sands</i>		<i>1</i>	<i>6</i>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<i>Gray clays & lime rock</i>		<i>6</i>	<i>23</i>	9. Casing: Material <i>PLTS</i> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <i>24</i> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <i>5</i> in. to <i>38</i> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <i>4"</i>		
<i>Fine to med sands & grando</i>		<i>23</i>	<i>30</i>	10. Screen: Manufacturer's name <i>Jet Stream</i> <i>Ralph Jones Co</i> Type <i>PVC</i> Dia. <i>5"</i> Slot/gauze <i>1/16"</i> Length <i>5'</i> Set between <i>36</i> ft. and <i>31</i> ft. ft. and <input type="checkbox"/> ft.		
<i>Shells of iron oxide</i>				Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>1/4" - 1/2"</i>		
<i>Fine to med sands - (very little iron)</i>		<i>30</i>	<i>35</i>	11. Static water level: <input type="checkbox"/> mo./day/yr. <i>14'-6"</i> ft. below land surface Date <i>10-23-75</i>		
<i>Red & green shale</i>		<i>35</i>	<i>38</i>	12. Pumping level below land surfaces: <i>15</i> ft. after <i>2</i> hrs. pumping <i>15</i> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <i>30</i> g.p.m.		
				13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <input type="checkbox"/>		
				14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <i>24</i> Inches above grade		
				15. Well grouted? <i>Yes</i> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <i>4</i> ft. to <i>14</i> ft.		
				16. Nearest source of possible contamination: <i>Barn</i> ft. <i>130</i> Direction <i>S.E.</i> Type <i>gaul.</i> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		<i>Mr. Johnson will pour concrete shel around the well. He understands this the law.</i>		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Peterson Bros Inc</i> <i>138</i> Business name License No. Address <i>Box 157 Salina, Kans</i> Signed <i>Kelly Peterson</i> Date <i>10-23-75</i> Authorized representative		