


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>NESS</b>	Fraction <b>SW 1/4 SE 1/4 SW 1/4</b>	Section number <b>27</b>	Township number <b>T 20 S R 22</b>	Range number <b>22</b>
2. Distance and direction from nearest town or city: <b>10 MI. NORTH</b> <b>1 1/4 MI. WEST FROM HANSTON, KANSAS</b> Street address of well location if in city:				3. Owner of well: <b>BARRICKLOW FARMS (CLETUS REIN)</b> R.R. or street: City, state, zip code: <b>BAZINE, KANSAS 67516</b>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>30</b> in. Completion date <b>30 April 78</b> Well depth <b>81</b> ft.		
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
BROWN CLAY				9. Casing: Material <b>STEEL</b> Height: Above or <b>300</b> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>18</b> in. to <b>41</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>288</b>		
SAND-VERY LITTLE CLAY				10. Screen: Manufacturer's name <b>W.A. BROWN ENTERPRISES</b> Type <b>STEEL</b> Dia. <b>16"</b> Slot/gauze <b>1/8</b> Length <b>40'</b> Set between <b>41</b> ft. and <b>81</b> ft. ft. and <b>1/2 DOWN</b> Gravel pack? <b>YES</b> Size range of material <b>30/60</b>		
TAN CLAY				11. Static water level: <input type="checkbox"/> mo./day/yr. <b>37</b> ft. below land surface Date <b>12/24/77</b>		
GOOD SAND AND GRAVEL				12. Pumping level below land surfaces: <b>50</b> ft. after <b>1/2</b> hrs. pumping <b>750</b> g.p.m. <b>57</b> ft. after <b>2</b> hrs. pumping <b>1000</b> g.p.m. Estimated maximum yield <b>1100</b> g.p.m.		
YELLOW CLAY				13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
BLUE SHALE				14. Well head completion: <input type="checkbox"/> Pitless adapter <b>18</b> inches above grade		
Brock 75				15. Well grouted? <b>YES</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>41</b> ft. to <b>11</b> ft.		
41 solid				16. Nearest source of possible contamination: <b>OIL</b> ft. <b>420</b> Direction <b>NORTH</b> Type <b>WELL</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Alluvium				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>WESTERN LAND ROLLER</b> Model number <b>8B-100</b> HP <b>44</b> Volts <input type="checkbox"/> Length of drop pipe <b>70</b> ft. capacity <b>1000</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>DEAN WATERHOUSE DRILLING 243</b> Business name <b>HANSTON, KANSAS</b> License No. <input type="checkbox"/> Address <b>HANSTON, KANSAS</b> Signed <b>Dean Waterhouse</b> Date <b>3/17/78</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley		REF: 12CASCADING WATER PREVENTS WELL FROM MAKING MORE WATER <b>2172</b> <b>8</b> <b>2094</b>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5