

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: NESS NW 1/4 NW 1/4 NE 1/4 14 T 20 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM NESS - 9 SOUTH ON 283 - TO RD 40, WEST 2 1/2 MILES

2 WATER WELL OWNER: FEENEY, JOHN
 RR#, St. Address, Box #: 16859 40 ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code: NESS CITY, KS 67560- Application Number: NSWW 3657

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 526 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 144 ft. below land surface measured on mo/day/yr 08/17/08
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 45 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 526 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 526 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 420 ft. to 520 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 75 ft., From 0 ft. to 0 ft.
 From 85 ft. to 526 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 6 ft. to 30 ft., From 75 ft. to 85 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHWEST How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 35 CALACHIE 32 TAN CLAY			
20	40	32 TAN CLAY 36 BLUE CLAY			
40	240	07 BLUE SHALE 08 ROCK LAYERS			
240	320	16 GRAY CLAY 08 ROCK LAYERS			
320	400	16 GRAY CLAY 08 ROCK LAYERS 29 SANDSTONE			
400	440	16 GRAY CLAY 25 RED CLAY 29 SANDSTONE			
440	526	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 08/18/08 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/27/08
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*