

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: McPherson		NE 1/4 NE 1/4 SE 1/4	17	T 20 S	R 3 W
Distance and direction from nearest town or city street address of well if located within city?					
3 miles South of McPherson, KS					
2 WATER WELL OWNER:		Neal Beam			
RR#, St. Address, Box # :		RR 1 Box 125		Board of Agriculture, Division of Water Resources	
City, State, ZIP Code :		McPherson, KS 67460		Application Number:	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 180 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 69 ft. below land surface measured on mo/day/yr 7/18/96			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 5 in. to 180 ft. and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 1X Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued X Clamped			
1 Steel 3 RMP (SR)		Welded			
X PVC 4 ABS		Threaded			
Blank casing diameter 2 in. to 163 ft. Dia 2" STEEL in. to 7 ft. Dia					
Casing height above land surface 12 in. weight 1.703 lbs./ft. Wall thickness or gauge No. 154					
TYPE OF SCREEN OR PERFORATION MATERIAL:		X PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
1 Continuous slot X Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 163 ft. to 180 ft. From ft. to ft.					
GRAVEL PACK INTERVALS: From 150 ft. to 180 ft. From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout X Bentonite 4 Other					
Grout Intervals: From 0 ft. to 150 ft. From ft. to ft. From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
X Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? North		How many feet? 150			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Top Soil			
2	5	Dark Gray Clay			
5	51	Tan Clay			
51	55	Medium Sand with Tan Clay layers			
55	104	Fine to Medium Sand			
104	110	Gray Clay			
110	130	Dark Gray Clay			
130	170	Fine to Medium Sand			
170	180	Fine to Medium Sand with Small Clay layers			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (X) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/18/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/yr) 8/9/96 under the business name of Peterson Irrigation, Inc. by (signature) Mike Peterson					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					