

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 086 SCOTT | NW 1/4 NE 1/4 NE 1/4 | 18 | T 20 S | R 32 W

Distance and direction from nearest town or city street address of well if located within city?
FROM SHALLOW WATER; APPX 3 MILES SOUTH & 3/4 MILE EAST

2 WATER WELL OWNER: **POKY FEEDERS, INC.**
 RR#, St. Address, Box # : **600 E. ROAD 30** Board of Agriculture, Division of Water Resources
 City, State, ZIP code : **SCOTT CITY, KS 67871-9412** Application Number: **22396 & 8869**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 193 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 95 ft. below land surface measured on mo/day/yr 7/26/07 Pump test data: Well water was 174 ft. after 1 hours pumping 96 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 20 in. to 193 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 02 IRRIGATION
Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: **02 PVC** CASING JOINTS: **GLUED**
 Blank casing diameter **10** in. to **193** ft., Dia in. to **0** ft., Dia in. to **0** ft.
 Casing height above land surface **12** in., weight **8** lbs/ft. Wall thickness or gauge No. **.365**
 TYPE OF SCREEN OR PERFORATION MATERIAL: **07 PVC**
 SCREEN OR PERFORATION OPENINGS ARE: **03 MILL SLOT**

SCREEN PERFORATED INTERVALS: From **113** ft. to **173** ft., From **0** ft. to **0** ft.
 From **0** ft. to **0** ft., From **0** ft. to **0** ft.
 GRAVEL PACK INTERVALS: From **20** ft. to **193** ft., From **0** ft. to **0** ft.
 From **0** ft. to **0** ft., From **0** ft. to **0** ft.

6 GROUT MATERIAL **03 BENTONITE**
 Grout Intervals: From **0** ft. to **20** ft., From **0** ft. to **0** ft., From **0** ft. to **0** ft.
 What is the nearest source of possible contamination: **14 ABAND. WELL**
 Direction from well? **NORTHWEST** How many feet? **110**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	24	04 SANDY CLAY 07 FINE SAND			
24	36	01 CLAY			
36	67	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
67	95	04 SANDY CLAY 05 SAND			
95	98	07 FINE SAND			
98	117	04 SANDY CLAY 07 FINE SAND			
117	146	07 FINE SAND 08 MEDIUM SAND			
146	153	07 FINE SAND 08 MEDIUM SAND			
153	160	07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **07/24/07** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **10/22/07** under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 086 SCOTT | NW 1/4 NE 1/4 NE 1/4 | 18 | T 20 S | R 32 W

2 WATER WELL OWNER: POKY FEEDERS, INC.
RR#, St. Address, Box # : 600 E. ROAD 30 Board of Agriculture, Division of Water Resources
City, State, ZIP code : SCOTT CITY, KS 67871-9412 Application Number: 22396 & 8869

FROM	TO	LITHOLOGIC LOG
160	173	07 FINE SAND 08 MEDIUM SAND
173	176	31 CALICHE
176	180	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/24/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/22/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

