

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: 086 SCOTT ; SW 1/4 NW 1/4 SW 1/4 ; 18 ; T 20 S ; R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 3/4 MILE SOUTH OF SHALLOW WATER

2 WATER WELL OWNER: POKY FEEDERS INC
 RR#, St. Address, Box #: RT 2, BOX 168 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SCOTT CITY, KS 67871- Application Number: 40,778

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: ; 4 DEPTH OF COMPLETED WELL 1020 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 320 ft. below land surface measured on mo/day/yr 06/05/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17.5 in. to 1020 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 8 in. to 1020 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 8 lbs/ft. Wall thickness or gauge No. .500
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 760 ft. to 1020 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 220 ft., From 0 ft. to 0 ft.
 From 230 ft. to 1020 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 220 ft. to 230 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: WATER WELL
 Direction from well? SOUTH How many feet? 250

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	5	01 CLAY			
5	14	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
14	22	01 CLAY			
22	28	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
28	36	01 CLAY			
36	87	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL			
87	107	04 SANDY CLAY			
102	116	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
116	128	31 CALICHE 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/11/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 086 SCOTT | SW 1/4 NW 1/4 SW 1/4 | 18 | T 20 S | R 32 W

2 WATER WELL OWNER: POKY FEEDERS INC
RR#, St. Address, Box #: RT 2, BOX 168 Board of Agriculture, Division of Water Resources
City, State, ZIP code: SCOTT CITY, KS 67871- Application Number: 40,778

FROM	TO	LITHOLOGIC LOG
128	136	04 SANDY CLAY 31 CALICHE
136	140	01 CLAY
140	152	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
152	166	01 CLAY 07 FINE SAND
166	184	07 FINE SAND 09 COARSE SAND 13 FINE GRAVEL
184	190	01 CLAY
190	294	19 SHALE
294	309	31 CALICHE 23 SANDSTONE
309	370	23 SANDSTONE 31 CALICHE
370	762	19 SHALE 20 LIMESTONE
762	1020	23 SANDSTONE 20 LIMESTONE 31 CALICHE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/05/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/11/93 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*