

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

SHALLOW WATER

2032W19CAD
T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

CAD

1 Location of well:	County SCOTT	Township name	Fraction SE-NESW	Section number 19	Town number 20S	Range number 32W
Distance and direction from nearest town or city: 12 3/4 S, 1/2 E of				3 Owner of well: Gary Skibbe		
Street address of well location if in city: C of Scott City				Address: RFD 2 Scott City, Kans. 67871		
Locate with "X" in section below:		Sketch map:				
N						
W — X — E						
		S 1 Mile				
2 Type and color of material			From	To		
Clay			0	50		
Fine sand			50	62		
Clay with some sand			62	80		
Fine sand with soft clay			80	100		
Sandy clay with soft rock			100	122		
Hard rock and gypsum			122	137		
Gyp + sandstone with some clay			137	145		
Sand with a little gyp.			145	155		
Sand with gyp + some loose gravel			155	159		
Sand			159	175		
Yellow + gravel			175	187		
Blue			187			
BROCK 175'						
(use a second sheet if needed)						
16 Remarks: elevation						
2918 (TOPO)						
Topography:						
<input type="checkbox"/> Hill						
<input type="checkbox"/> Slope						
<input checked="" type="checkbox"/> Upland						
<input type="checkbox"/> Valley						
4 Well depth: 187 ft. Date of completion 6-10-75			Well diameter 7 3/8 in.			
5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary						
6 Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>						
7 Casing: Material ABS Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. Weight ___ lbs./ft. — 5 in. to 167 ft. depth Drive shaft? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No ___ in. to ___ ft. depth 12 1/2" well						
8 Screen: Manufacturer Jess + Lowell Type ABS Dia. 5" I.D. Slot gauze 110 Length 20 ft. Set between 167 ft. and 187 ft. — Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 5/8 down						
9 Static water level: 110 ft. below land surface Date 4-15-75						
10 Pumping level below land surfaces: 120 ft. after 2 hrs. pumping 10 g.p.m. ___ ft. after ___ hrs. pumping ___ g.p.m. Estimated maximum yield 100 g.p.m.						
11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ___						
12 Well head completion: <input checked="" type="checkbox"/> Pitless adapter unit <input type="checkbox"/> Inches above grade						
13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> ___ Depth: From 0 ft. to 20 ft.						
14 Nearest source of possible contamination: 300 ft. Direction West Type Septic tank Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No						
15 Pump: <input type="checkbox"/> Not installed Manufacturer's name PUMPO Model number 1025 104 HP 1 Volts 230 Length of drop pipe 184 ft. capacity 10 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other						
17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. ABC Drilling Co. 246 Business name License No. ___ Address Scott City, Ks. 67871 Signed Dell Nottingham 7-3-75 Authorized representative						