

WATER WELL RECORD Form WWC-5 KSA 82a-121Z

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 086 SCOTT NW 1/4 NE 1/4 NW 1/4 24 T 20 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 1/2 MILES NORTH & 3/4 MILE WEST OF FRIEND

2 WATER WELL OWNER: CHENEY, HOWARD E. Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: 12500 S KS RD Application Number: 26.626
 City, State, ZIP code: SCOTT CITY, KS 67871-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 191 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 124 ft. below land surface measured on mo/day/yr 05/27/97
 Pump test data: Well water was 160 ft. after 4 hours pumping 745 gpm
 Estimated Yield 745 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 191 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No :
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 191 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 39 lbs/ft. Wall thickness or gauge No. .225
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT
 SCREEN PERFORATED INTERVALS: From 141 ft. to 181 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 170 ft., From 0 ft. to 0 ft.
 From 170 ft. to 191 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 102

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	51	01 CLAY			
51	74	01 CLAY 36 GYP ROCK			
74	83	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL			
83	96	01 CLAY 36 GYP ROCK			
96	102	05 SAND 11 GRAVEL 01 CLAY			
102	112	36 GYP ROCK 01 CLAY 05 SAND			
112	122	36 GYP ROCK 01 CLAY			
122	134	01 CLAY 36 GYP ROCK 05 SAND			
134	142	08 MEDIUM SAND 09 COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/21/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/06/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 086 SCOTT	NW 1/4 NE 1/4 NW 1/4	24	T 20 S	R 33 W

2 WATER WELL OWNER:	CHENEY, HOWARD E.	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	12500 S KS RD	

City, State, ZIP code :	SCOTT CITY, KS 67871-	Application Number: 26,626
-------------------------	-----------------------	----------------------------

FROM	TO	LITHOLOGIC LOG
142	173	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
173	181	07 FINE SAND 08 MEDIUM SAND
181	185	31 CALICHE
185	186	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/21/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/06/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichmuth