

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 086 SCOTT SW 1/4 NW 1/4 SW 1/4 13 T 20 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM SHALLOW WATER; APPX 3 1/2 MILES SOUTH

2 WATER WELL OWNER: CRIST FREEDYARD, INC.
 RR#, St. Address, Box # : 533 W. ROAD 40 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SCOTT CITY, KS 67871-5038 Application Number: 3037 & SC98

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \		NW	NE			
1	---	---	---	---	---	---
M	W	---	---	---	---	E
i	---	---	---	---	---	---
l	---	---	---	---	---	---
e	X	SW	SE	---	---	---
\ /	---	---	---	---	---	---

4 DEPTH OF COMPLETED WELL 200ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 138 ft. below land surface measured on mo/day/yr 10/17/05
 Pump testdata: Well water was 166 ft. after 4 hours pumping 350 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 200 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 141 ft. to 181 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 200 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 101

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	20	01 CLAY 05 SAND 31 CALICHE			
20	80	01 CLAY			
80	100	05 SAND 11 GRAVEL			
100	123	01 CLAY 20 LIMESTONE 05 SAND			
123	140	07 FINE SAND 08 MEDIUM SAND			
140	160	05 SAND 13 FINE GRAVEL			
160	170	07 FINE SAND 08 MEDIUM SAND			
170	180	05 SAND 13 FINE GRAVEL			
180	184	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/08/05 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/12/06
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 086 SCOTT	Fraction SW 1/4 NW 1/4 SW 1/4	Section Number 13	Township Number T 20 S	Range Number R 33 W
--	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: CRIST FEEDYARD, INC.
RR#, St. Address, Box # : 533 W. ROAD 40
City, State, ZIP code : SCOTT CITY, KS 67871-5038

Board of Agriculture, Division of Water Resources
Application Number: 3037 & SC98

FROM	TO	LITHOLOGIC LOG
184	200	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/08/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/12/06 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Brian J. Reichenbach*