

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment
Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Scott	Fraction NW 1/4 NE 1/4 NW 1/4	Section number 21	Township number T 20 S R 33 E/W	Range number
2. Distance and direction from nearest town or city: 11 S & 5 W of Scott City Street address of well location if in city:			3. Owner of well: Albert Savolt R.R. or street: 2120 Buffalo Heights City, state, zip code: Garden City, Kansas 67846		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>28</u> in. Completion date <u>16 Feb. 76</u> Well depth <u>160</u> ft.	
		1210' W & 352' S of NE corner of NW 1/4, Sec. 21, T20S, R33W, Scott County, Kansas		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
5. Type and color of material			From	To	9. Casing: Material <u>Stl</u> Height: <u>Above or below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>37</u> lbs./ft. Dia. <u>16</u> in. to <u>100</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>.219</u>
Top soil			0	4	10. Screen: Manufacturer's name <u>Layne & Foster</u> <u>Louver & Millslot</u> <u>16"</u> Type Dia. Slot/gauze <u>1/8"</u> Length <u>60'</u> Set between <u>100</u> ft. and <u>160</u> ft. <u> </u> ft. and <u> </u> ft.
Tan clay, sand streaks			4	63	Gravel pack? <input checked="" type="checkbox"/> yes Size range of material <u>4.4mm</u>
Limestone			63	83	11. Static water level: <u>108</u> ft. below land surface Date <u>12-12-75</u> mo./day/yr.
Fine to coarse sand, limestone streaks, tight sand streaks			83	100	12. Pumping level below land surfaces: <u>134</u> ft. after <u>1</u> hrs. pumping <u>586</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>600</u> g.p.m.
Fine to coarse sand, firm			100	149	13. Water sample submitted: <u> </u> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u> </u>
Fine to coarse sand, fine gravel			149	159	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
Black shale			159	160	15. Well grouted? <input checked="" type="checkbox"/> yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
(Use a second sheet if needed)					16. Nearest source of possible contamination: <u>Unk</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
					17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Layne & Bowler</u> Model number <u>10KEH</u> HP <u>50</u> Volts <u> </u> Length of drop pipe <u>150</u> ft. capacity <u>550</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Layne-Western Co., Inc.</u> License No. <u>150</u> Business name <u>Garden City, Kansas</u> Address <u> </u> Signed <u> </u> Date <u>24 May 76</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

20
33
21
NEW
NEW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5