

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Scott</b>	Fraction <b>SW 1/4 SE 1/4 NW 1/4</b>	Section number <b>36</b>	Township number <b>T 20 S R 33 E/W</b>	Range number
2. Distance and direction from nearest town or city: <b>14 Miles south of Scott City, Kansas</b> Street address of well location if in city:				3. Owner of well: <b>N-Ren Corporation</b> R.R. or street: <b>256 McCullough Street</b> City, state, zip code: <b>Cincinnati, Ohio</b>		
4. Locate with "X" in section below:				Sketch map:		6. Bore hole dia. <b>28</b> in. Completion date <b>8-30-76</b> Well depth <b>148</b> ft.
		Sketch map: <b>330' E &amp; 660' N of the SW corner of E 1/2 of NW 1/4, Sec. 36, T20S, R33W, Scott County, Kansas.</b>				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
						8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
5. Type and color of material				From	To	9. Casing: Material <b>Stl.</b> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>12</b> in. to <b>118</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>.312</b>
<b>Top soil</b>				<b>0</b>	<b>4</b>	10. Screen: Manufacturer's name <b>Cook</b> Type <b>Wirewrap</b> Dia. <b>12"</b> Slot/gauze <b>1/8"</b> Length <b>37</b> Set between <b>118</b> ft. and <b>148</b> ft. _____ ft. and _____ ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>4.4 mm</b>
<b>Tan clay</b>				<b>4</b>	<b>36</b>	11. Static water level: _____ mo./day/yr. <b>72</b> ft. below land surface Date <b>1-12-76</b>
<b>Tan clay sand streaks</b>				<b>36</b>	<b>46</b>	12. Pumping level below land surfaces: <b>120</b> ft. after <b>7</b> hrs. pumping <b>901</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>1000</b> g.p.m.
<b>Tan sandy clay</b>				<b>46</b>	<b>98</b>	13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____
<b>Limestone</b>				<b>98</b>	<b>112</b>	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
<b>Tan clay</b>				<b>112</b>	<b>118</b>	15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
<b>Coarse sand fine to medium gravel loose</b>				<b>118</b>	<b>142</b>	16. Nearest source of possible contamination: <b>unk</b> ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
<b>small clay streaks</b>						17. Pump: _____ Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>10RKHC</b> HP <b>40</b> Volts <b>460</b> Length of drop pipe <b>140</b> ft. capacity <b>500</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
<b>Yellow clay black shale</b>				<b>142</b>	<b>160</b>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Company, Inc.</b> Business name _____ License No. _____ Address <b>Garden City, Kansas</b> Signed <b>[Signature]</b> Date <b>8/1/76</b> Authorized representative
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

20  
33  
36  
S  
E  
W  
N  
1/4  
1/4  
1/4  
1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5