

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Scott</b>	Fraction <b>SE 1/4 NW 1/4 SE 1/4</b>	Section number <b>36</b>	Township number <b>T 20 S R 33 E/W</b>	Range number <b>33</b>
2. Distance and direction from nearest town or city: <b>14 Miles south of Scott City, Kansas.</b> Street address of well location if in city:				3. Owner of well: <b>N-Ren Corporation</b> R.R. or street: <b>256 McCullough Street</b> City, state, zip code: <b>Cincinnati, Ohio 45226</b>		
4. Locate with "X" in section below:				Sketch map:		6. Bore hole dia. <b>28</b> in. Completion date <b>8-30-76</b> Well depth <b>155</b> ft.
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
5. Type and color of material				From	To	9. Casing: Material <b>Stl.</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>2 1/2</b> in. to <b>12 1/2</b> in. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>XXXX</b> .312
Top soil				0	4	10. Screen: Manufacturer's name <b>Cook</b> Type <b>wirewrap</b> Dia. <b>12"</b> Slot/gauze <b>1/8"</b> Length <b>30</b> Set between <b>125</b> ft. and <b>155</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>4.4mm</b>
Tan clay				4	48	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>75</b> ft. below land surface Date <b>1-10-76</b>
Fine to coarse sand				48	50	12. Pumping level below land surfaces: <b>136</b> ft. after <b>2</b> hrs. pumping <b>862</b> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>970</b> g.p.m.
Tan clay				50	107	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <input type="checkbox"/>
Limestone				107	125	14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade
Coarse sand fine gravel clay streaks				125	154	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Yellow clay black shale				154	180	16. Nearest source of possible contamination: <b>unk</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
(Use a second sheet if needed)						17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>10RKHC</b> HP <b>40</b> Volts <b>460</b> Length of drop pipe <b>140</b> ft. capacity <b>500</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne-Western Co., Inc. 102</b> Business name License No. Address <b>Garden City, Kansas</b> Signed <i>[Signature]</i> Date <b>18 Nov 76</b> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

20  
 33 E  
 36 SE  
 NWSE  
 Sec 1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5