

1. Location of well: <div style="font-size: 1.2em; font-family: cursive;">McPherson</div>		Fraction <div style="font-size: 1.2em; font-family: cursive;">Center 1/4 SW 1/4</div>		Section number <div style="font-size: 1.2em; font-family: cursive;">11</div>		Township number <div style="font-size: 1.2em; font-family: cursive;">T 20</div>		Range number <div style="font-size: 1.2em; font-family: cursive;">S 4 R 4</div>	
2. Distance and direction from nearest town or city: <div style="font-size: 1.2em; font-family: cursive;">2 mi NORTH</div>				3. Owner of well: <div style="font-size: 1.2em; font-family: cursive;">KENNETH WALKER</div>					
Street address of well location if in city: <div style="font-size: 1.2em; font-family: cursive;">OF GROVELAND</div>				R.R. or street: <div style="font-size: 1.2em; font-family: cursive;">406 So. ELM</div>					
				City, state, zip code: <div style="font-size: 1.2em; font-family: cursive;">McPherson Ks. 67460</div>					
4. Locate with "X" in section below: <div style="text-align: center;">N</div> <div style="display: flex; align-items: center; justify-content: center;"><div style="text-align: center; margin-right: 10px;">1 Mile ↑ W ↓ 1 Mile</div><div style="border: 1px solid black; padding: 5px; text-align: center; margin: 0 10px;">NW NE SW SE</div><div style="text-align: center; margin-left: 10px;">E ↓ 1 Mile S</div></div>				Sketch map:		6. Bore hole dia. <div style="font-size: 1.2em; font-family: cursive;">30</div> in. Completion date <div style="font-size: 1.2em; font-family: cursive;">12-31-78</div> Well depth <div style="font-size: 1.2em; font-family: cursive;">208</div> ft.			
<div style="font-size: 1.5em; font-family: cursive; transform: rotate(-30deg); display: inline-block;">IRRIGATION WELL</div>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		9. Casing: Material <div style="font-size: 1.2em; font-family: cursive;">TRANSITE</div> Weight: <div style="font-size: 1.2em; font-family: cursive;">12</div> in. Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <div style="font-size: 1.2em; font-family: cursive;">12</div> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <div style="font-size: 1.2em; font-family: cursive;">32</div> lbs./ft. Dia. <div style="font-size: 1.2em; font-family: cursive;">16</div> in. to <div style="font-size: 1.2em; font-family: cursive;">143</div> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gauge No. <div style="font-size: 1.2em; font-family: cursive;">3510</div>			
		10. Screen: Manufacturer's name <div style="font-size: 1.2em; font-family: cursive;">Aurora Tile Company</div> Type <div style="font-size: 1.2em; font-family: cursive;">TRANSITE</div> Dia. <div style="font-size: 1.2em; font-family: cursive;">16" I.D.</div> Slot/gauze <div style="font-size: 1.2em; font-family: cursive;">1/8</div> Length <div style="font-size: 1.2em; font-family: cursive;">65 ft</div> Set between <div style="font-size: 1.2em; font-family: cursive;">143</div> ft. and <div style="font-size: 1.2em; font-family: cursive;">208</div> ft. Gravel pack? <div style="font-size: 1.2em; font-family: cursive;">YES</div> Size range of material <div style="font-size: 1.2em; font-family: cursive;">14</div>		11. Static water level: <div style="font-size: 1.2em; font-family: cursive;">55</div> ft. below land surface Date <div style="font-size: 1.2em; font-family: cursive;">12-27-78</div>					
		12. Pumping level below land surfaces: <div style="font-size: 1.2em; font-family: cursive;">55</div> ft. after <div style="font-size: 1.2em; font-family: cursive;">1</div> hrs. pumping <div style="font-size: 1.2em; font-family: cursive;">1500</div> g.p.m. <div style="font-size: 1.2em; font-family: cursive;">72</div> ft. after <div style="font-size: 1.2em; font-family: cursive;">1</div> hrs. pumping <div style="font-size: 1.2em; font-family: cursive;">1500</div> g.p.m. Estimated maximum yield <div style="font-size: 1.2em; font-family: cursive;">1500</div> g.p.m.		13. Water sample submitted: <div style="font-size: 1.2em; font-family: cursive;">110</div> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <div style="font-size: 1.2em; font-family: cursive;">11/3</div>					
		14. Well head completion: <input type="checkbox"/> Pitless adapter <div style="font-size: 1.2em; font-family: cursive;">12</div> Inches above grade		15. Well grouted? <div style="font-size: 1.2em; font-family: cursive;">YES</div> <div style="font-size: 1.2em; font-family: cursive;">MIDDLE CLAY</div> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <div style="font-size: 1.2em; font-family: cursive;">0</div> ft. to <div style="font-size: 1.2em; font-family: cursive;">10</div> ft.					
5. Type and color of material		From		To		16. Nearest source of possible contamination: ft. <div style="font-size: 1.2em; font-family: cursive;">155</div> Direction <div style="font-size: 1.2em; font-family: cursive;">NONE WITHIN 2 miles</div> Type <div style="font-size: 1.2em; font-family: cursive;">NONE</div> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<div style="font-size: 1.2em; font-family: cursive;">Top Soil</div>		<div style="font-size: 1.2em; font-family: cursive;">0</div>		<div style="font-size: 1.2em; font-family: cursive;">5</div>		17. Pump: <div style="font-size: 1.2em; font-family: cursive;">Not installed</div> Manufacturer's name <div style="font-size: 1.2em; font-family: cursive;">WESTERN LAND ROLLER</div> Model number <div style="font-size: 1.2em; font-family: cursive;">110</div> HP <div style="font-size: 1.2em; font-family: cursive;">60</div> Volts <div style="font-size: 1.2em; font-family: cursive;">1400</div> g.p.m. Length of drop pipe <div style="font-size: 1.2em; font-family: cursive;">110</div> ft. capacity <div style="font-size: 1.2em; font-family: cursive;">1400</div> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
<div style="font-size: 1.2em; font-family: cursive;">Brown Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">5</div>		<div style="font-size: 1.2em; font-family: cursive;">17</div>					
<div style="font-size: 1.2em; font-family: cursive;">Red Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">17</div>		<div style="font-size: 1.2em; font-family: cursive;">32</div>					
<div style="font-size: 1.2em; font-family: cursive;">Buff Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">32</div>		<div style="font-size: 1.2em; font-family: cursive;">50</div>					
<div style="font-size: 1.2em; font-family: cursive;">FINE SAND</div>		<div style="font-size: 1.2em; font-family: cursive;">50</div>		<div style="font-size: 1.2em; font-family: cursive;">72</div>					
<div style="font-size: 1.2em; font-family: cursive;">Brown Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">72</div>		<div style="font-size: 1.2em; font-family: cursive;">77</div>					
<div style="font-size: 1.2em; font-family: cursive;">MEDIUM SAND</div>		<div style="font-size: 1.2em; font-family: cursive;">77</div>		<div style="font-size: 1.2em; font-family: cursive;">110</div>					
<div style="font-size: 1.2em; font-family: cursive;">GREEN Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">110</div>		<div style="font-size: 1.2em; font-family: cursive;">113</div>					
<div style="font-size: 1.2em; font-family: cursive;">Brown Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">113</div>		<div style="font-size: 1.2em; font-family: cursive;">132</div>					
<div style="font-size: 1.2em; font-family: cursive;">MEDIUM SAND WITH GREEN Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">132</div>		<div style="font-size: 1.2em; font-family: cursive;">155</div>					
<div style="font-size: 1.2em; font-family: cursive;">MEDIUM COURSE SAND</div>		<div style="font-size: 1.2em; font-family: cursive;">155</div>		<div style="font-size: 1.2em; font-family: cursive;">195</div>					
<div style="font-size: 1.2em; font-family: cursive;">MEDIUM SAND</div>		<div style="font-size: 1.2em; font-family: cursive;">195</div>		<div style="font-size: 1.2em; font-family: cursive;">204</div>					
<div style="font-size: 1.2em; font-family: cursive;">Red Clay</div>		<div style="font-size: 1.2em; font-family: cursive;">204</div>		<div style="font-size: 1.2em; font-family: cursive;">208</div>					