


USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | | |
|---|-----------------------|---|--|--------------------------------|--|--|
| 1. Location of well: | County Rice | Fraction NE 1/4 NE 1/4 SW 1/4 | Section number 13 | Township number T 20 | Range number S R 8 | E W |
| 2. Distance and direction from nearest town or city: 3 1/2 miles Southeast of Lyons, KS Street address of well location if in city: | | | 3. Owner of well: Cecil Miller, etal * R.R. or street: Route 1 City, state, zip code: Lyons, KS 67554 | | | |
| 4. Locate with "X" in section below:  | | | Sketch map: 2620' East - 2630 North SW Corner 13 Test Well No. 15 | | | 6. Bore hole dia. 5 in. Completion date 12-23-77 Well depth 67 ft. |
| 5. Type and color of material | | | From | To | 7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary | |
| Top soil | | | 0 | 3 | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input checked="" type="checkbox"/> Other Test Well | |
| Brown & gray clay | | | 3 | 9 | 9. Casing: Material PVC Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 2.2 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight .631 lbs./ft. Dia. 2 1/2 in. to 57 ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No. .110 | |
| Sand & gravel | | | 9 | 31 | 10. Screen: Manufacturer's name Clarke Type PVC Dia. 2 1/2 " Slot/gauze 1/8" Length 10' Set between 57 ft. and 67 ft. ft. and ft. Gravel pack? Yes Size range of material 1/4" | |
| Yellow clay | | | 31 | 34 | 11. Static water level: _____ mo./day/yr. 14 ft. below land surface Date 3-17-78 | |
| Sand & gravel | | | 34 | 67 | 12. Pumping level below land surfaces: Not Checked _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m. | |
| Red shale | | | 67 | 70 | 13. Water sample submitted: Chl-12, 600 no./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 12-23-77 | |
| | | | | | 14. Well head completion: <input type="checkbox"/> Pitless adapter _____ Inches above grade | |
| | | | | | 15. Well grouted? NO ** With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From _____ ft. to _____ ft. | |
| | | | | | 16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | |
| | | | | | 17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | |
| | | | (Use a second sheet if needed) | | | |
| 18. Elevation: (Ground) 1640.6' Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley | | 19. Remarks: * Work performed on behalf of Cecil Miller etal to obtain ground water information RE: Miller vs. Cudahay lawsuit. ** Test wells were considered temporary when drilled. Due to pending litigation, a decision to plug wells or grout and establish permanent observation wells has not been made. | | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name _____ License No. _____ Address Great Bend, KS 67530 Signed _____ Date 8-25-78 Authorized representative | |

80
 13
 NE
 1/4
 1/4
 1/4
 SW