


1 LOCATION OF WATER WELL: Fraction Near 1/4 C 1/4 SE 1/4 Section Number 30 Township Number T 20 S Range Number R 8 EW  
 County: Rice

Distance and direction from nearest town or city street address of well if located within city?  
4 north, 1 3/4 west of Sterling

2 WATER WELL OWNER: Eugene Pearson  
 RR#, St. Address, Box #: Rt. 1, Box 29 Board of Agriculture, Division of Water Resources  
 City, State, ZIP Code: Sterling, Ks. 67579 Application Number: 36,394

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  DEPTH OF COMPLETED WELL: 67 ft. ELEVATION: 4 ft.  
 Depth(s) Groundwater Encountered 1. 19 ft. 2. 4 ft. 3. 12-17-82 ft.  
 WELL'S STATIC WATER LEVEL 19 ft. below land surface measured on mo/day/yr 12-17-82  
 Pump test data: Well water was 43 ft. after 1 hours pumping 1100 gpm  
 Est. Yield 1000 gpm: Well water was 50 ft. after 1 1/2 hours pumping 1400 gpm  
 Bore Hole Diameter: 29 in. to 67 ft., and          in. to          ft.  
 WELL WATER TO BE USED AS:  
 1 Domestic 2 Irrigation 3 Feedlot 4 Industrial 5 Public water supply 6 Oil field water supply 7 Lawn and garden only 8 Air conditioning 9 Dewatering 10 Observation well 11 Injection well 12 Other (Specify below)  
 Was a chemical/bacteriological sample submitted to Department? Yes          No X; If yes, mo/day/yr sample was submitted           
 Water Well Disinfected? Yes HTH No         

5 TYPE OF BLANK CASING USED:  
 1 Steel          3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued          Clamped           
 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded X  
 7 Fiberglass Threaded           
 Blank casing diameter 16 in. to 47 ft., Dia          in. to          ft., Dia          in. to          ft.  
 Casing height above land surface 24 in., weight          lbs./ft. Wall thickness or gauge No. 7  
 TYPE OF SCREEN OR PERFORATION MATERIAL:  
 1 Steel          3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement  
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)           
 12 None used (open hole)  
 SCREEN OR PERFORATION OPENINGS ARE:  
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)  
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes  
 7 Torch cut 10 Other (specify)           
 SCREEN-PERFORATED INTERVALS: From 47 ft. to 67 ft., From          ft. to          ft.  
 From          ft. to          ft., From          ft. to          ft.  
 GRAVEL PACK INTERVALS: From 10 ft. to 67 ft., From          ft. to          ft.  
 From          ft. to          ft., From          ft. to          ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other           
 Grout Intervals: From 0 ft. to 10 ft., From          ft. to          ft., From          ft. to          ft.  
 What is the nearest source of possible contamination:  
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well  
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well  
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)  
 13 Insecticide storage  
 Direction from well?          How many feet? NONE

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	o4 Sandy top soil			
2	16	o1 Brown clay-soft w/streaks of fine gravel			
16	67	// Big gravel			
67		o1 Soft brown clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-28-83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/yr) 5-17-83 under the business name of Rosencrantz-Bemis Ent. by (signature) Abra Dodson

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

\$1.00 Perennial Record DP

OFFICE USE ONLY  
 T  
 20  
 R  
 30  
 SEC.  
 30  
 C 1/4 SE 1/4