

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.


T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Rice	Township name	Fraction C/SE$\frac{1}{4}$	Section number 31	Town number 20	Range number 9
---------------------	-----------------------	---------------	---	-----------------------------	--------------------------	--------------------------

Distance and direction from nearest town or city: 5$\frac{1}{2}$ miles south of Chase, Ks. Street address of well location if in city:	3 Owner of well: Address: John Caywood Alden, Kansas
--	---

Locate with "X" in section below: N  W E S	Sketch map:	4 Well depth: 60 ft. Date of completion 1-8-75 Well diameter 7 7/8 in.
		5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
		6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input checked="" type="checkbox"/> Test well <input type="checkbox"/> test hole for irrigat
		7 Casing: Material pvc Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 15 in. above Diam. Weight 160 lbs./ft. 4 in. to 40 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No — in. to — ft. depth

2 Type and color of material	From	To	
Top soil	0	2	
Sandy brown clay	2	5	
Sand & gravel clean, coarse, loose	5	29	
Brown & blue clay	29	36	
Sand & gravel clean, coarse, loose	36	58	
Yellow brown clay	58	59 $\frac{1}{2}$	
Blue clay	59 $\frac{1}{2}$	60	
Red bed	60		
(use a second sheet if needed)			

8 Screen: Manufacturer R & B Type pvc Dia. 4 Slot 1/16 Length 20' Set between 40 ft. and 60 ft. 20 Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 3/4-3/8-1/16
9 Static water level: 6 ft. below land surface Date 1-8-75

10 Pumping level below land surfaces: 18 ft. after 1 hrs. pumping 75 g.p.m. — ft. after — hrs. pumping — g.p.m. Estimated maximum yield 100 g.p.m.
--

11 Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 1-8-75
--

12 Well head completion: <input type="checkbox"/> Pitless adapter 15 inches above grade

13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From 0 ft. to 10 ft.
--

14 Nearest source of possible contamination: ft. 1500 Direction NE Type corral Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No HTH
--

15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
--

16 Remarks: elevation
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley

17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Ks. Signed Fredia Dodson Date 1-9-75 Authorized representative
--