


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: McPherson		SE 1/4 NE 1/4 SE 1/4	9	T 21 S	R 1
Distance and direction from nearest town or city street address of well if located within city? 9 1/2 miles South of Canton, KS					
2 WATER WELL OWNER: Melvin Miller					
RR#, St. Address, Box # : R.R. Box 46			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Moundridge, KS 67107			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 44 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1 ft. 7 ft. 2 ft. 3 ft.			
		WELL'S STATIC WATER LEVEL 7 ft. below land surface measured on mo/day/yr 5-5-93			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield 1.0 gpm: Well water was 2.1 ft. after 1 hours pumping 6 gpm			
Bore Hole Diameter: 8 in. to 44 ft., and _____ in. to _____ ft.		WELL WATER TO BE USED AS:			
1 Domestic		3 Feedlot	6 Oil field water supply	9 Dewatering	12 Other (Specify below)
2 Irrigation		4 Industrial	7 Lawn and garden only	10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes _____ No X ; If yes, mo/day/yr sample was submitted _____					
Water Well Disinfected? Yes X No _____					
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	
2 PVC		4 ABS	7 Fiberglass		
Blank casing diameter 5 in. to 24 ft., Dia 34 in. to 44 ft., Dia _____ in. to _____ ft.					
Casing height above land surface 1.2 in., weight 2.37 lbs./ft. Wall thickness or gauge No. 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 24 ft. to 34 ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From 20 ft. to 44 ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL:					
1 Neat cement		2 Cement grout	3 Bentonite	4 Other	
Grout Intervals: From 0 ft. to 20 ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
13 Insecticide storage					
Direction from well? West		How many feet? 75 ft			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Top Soil			
2	12	Tan Clay			
12	14	Fine Sand			
14	15	Tan Clay			
15	25	Fine Sandy Clay			
25	29	Fine Sand			
29	31	Tan Clay			
31	35	Sandy Clay			
35	42	Light Green Clay			
42	44	Green Shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-5-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 . This Water Well Record was completed on (mo/day/yr) 5-6-93 under the business name of Peterson Irrigation Inc. by (signature) <i>Mike Peterson</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					