

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Rice	Fraction 1/4	Center 1/4NW 1/4	Section number 1	Township number T 21 S	Range number R 10 EW
2. Distance and direction from nearest town or city: 3 miles Southeast of Raymond, KS Street address of well location if in city:				3. Owner of well: John Keely R.R. or street: P.O. Box 127 City, state, zip code: Sterling, KS 67579			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>24</u> in. Completion date <u>7-7-77</u> Well depth <u>30</u> ft. Each Well			
		<p>NOTE NOTE: This is a manifold system, 5 wells, 50' apart with manifold located @ described location. Only this report will be filed for all 5 wells.</p>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
5. Type and color of material		From	To	9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>10</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>			
Top Soil		0	4	10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot gauge <u>1/8</u> Length <u>20</u> Set between <u>10</u> ft. and <u>30</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>			
SAnd & gravel		4	29	11. Static water level: <u>10'</u> ft. below land surface Date <u>3-10-77</u> mo./day/yr.			
Yellow clay		29	30	12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u>N/C</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.			
				13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>			
				14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> Inches above grade			
				15. Well grouted? <u>yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.			
				16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>B4JRBM Berkeley</u> Model number <u>B4JRBM</u> HP <u>40</u> Volts <u>460</u> Length of drop pipe <u>25' ea</u> ft. capacity <u>800</u> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input checked="" type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
				(Use a second sheet if needed)			
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u> </u> Address <u> </u> Signed <u>O.W. [Signature]</u> Date <u>7-7-77</u> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley							

21 L O W - 1
T
R
E
C
1/4 1/4 1/4 1/4