

1] LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Stafford	NW ¼ SE ¼ NE ¼	18	T 21 S	R 13 XW

Distance and direction from nearest town or city street address of well if located within city?
6 1/2 north of Seward, KS

2] WATER WELL OWNER: **American Warrior Inc.** SFWW2071
 RR#, St. Address, Box # : **P.O. Box 399** Board of Agriculture, Division of Water Resources
 City, State, ZIP Code : **Garden City, KS 67846-8399** Application Number: **20010214**

3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4] DEPTH OF COMPLETED WELL: **90** ft. ELEVATION: _____ ft.
 Depth(s) Groundwater Encountered **1** ft. **2** ft. **3** ft.
 WELL'S STATIC WATER LEVEL **28** ft. below land surface measured on **mo/day/yr 10-9-01**
 Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm
 Est. Yield **NA** gpm: Well water was _____ ft. after _____ hours pumping _____ gpm
 Bore Hole Diameter **9 7/8** in. to **90** ft., and _____ in. to _____ ft.
 WELL WATER TO BE USED AS: **5** Public water supply **8** Air conditioning **11** Injection well
1 Domestic **3** Feedlot **6** Oil field water supply **9** Dewatering **12** Other (Specify below)
2 Irrigation **4** Industrial **7** Domestic (lawn & garden) **10** Monitoring well _____
 Was a chemical/bacteriological sample submitted to Department? Yes _____ No **X**; If yes, mo/day/yrs sample was submitted
 Water Well Disinfected? Yes **HTH** No

5] TYPE OF BLANK CASING USED: **5** Wrought iron **8** Concrete tile CASING JOINTS: Glued **X** Clamped _____
1 Steel **3** RMP (SR) **6** Asbestos-Cement **9** Other (specify below) Welded _____
2 PVC **4** ABS **7** Fiberglass _____ Threaded _____
 Blank casing diameter **5** in. to **70** ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.
 Casing height above land surface **24** in., weight **SDR-26** lbs./ft. Wall thickness or gauge No. _____

TYPE OF SCREEN OR PERFORATION MATERIAL: **7** PVC **10** Asbestos-cement
1 Steel **3** Stainless steel **5** Fiberglass **8** RMP (SR) **11** Other (specify) _____
2 Brass **4** Galvanized steel **6** Concrete tile **9** ABS **12** None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE: **5** Gauzed wrapped **8** Saw cut **11** None (open hole)
1 Continuous slot **3** Mill slot **6** Wire wrapped **9** Drilled holes
2 Louvered shutter **4** Key punched **7** Torch cut **10** Other (specify) _____ ft.
 SCREEN-PERFORATED INTERVALS: From **90** ft. to **70** ft., From _____ ft. to _____ ft.
 From _____ ft. to _____ ft., From _____ ft. to _____ ft.
 GRAVEL PACK INTERVALS: From **90** ft. to **20** ft., From _____ ft. to _____ ft.
 From _____ ft. to _____ ft., From _____ ft. to _____ ft.

6] GROUT MATERIAL: **1** Neat cement **2** Cement grout **3** Bentonite **4** Other **hole plug**
 Grout Intervals: From **20** ft. to **0** ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.
 What is the nearest source of possible contamination:
1 Septic tank **4** Lateral lines **7** Pit privy **10** Livestock pens **14** Abandoned water well
2 Sewer lines **5** Cess pool **8** Sewage lagoon **11** Fuel storage **15** Oil well/Gas well
3 Watertight sewer lines **6** Seepage pit **9** Feedyard **12** Fertilizer storage **16** Other (specify below)
13 Insecticide storage **None**
 Direction from well? _____ How many feet? _____

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	sandy top soil			
2	8	fine sand			
8	18	sandy reddish brown clay			
18	29	fine sand and sandy reddish brown clay mix			
29	44	tan clay			
44	53	gray and tan clay			
53	58	sand and gravel and clay mix			
58	76	sand and gravel clean, medium, loose, clay streaks			
76	87	sand and gravel clean, medium, loose			
87	90	sand and gravel clean, medium, loose, clay streaks			

7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **10-9-01** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No. **134** This Water Well Record was completed on (mo/day/yr) **10-31-01** under the business name of **Rosencrantz-Bemis** by (signature) *Theresa Hedson*