


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Stafford</b>	Fraction <b>1/4 1/4 CSW 1/4</b>	Section number <b>17</b>	Township number <b>T 21 S</b>	Range number <b>R 14 E</b>
2. Distance and direction from nearest town or city: <b>3 miles North of Radium</b> Street address of well location if in city:			3. Owner of well: <b>Pete Kirkman</b> R.R. or street: <b>1909 Lincoln</b> City, state, zip code: <b>Great Bend, KS 67530</b>		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W  E S 1 Mile</div>			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <b>24</b> in. Completion date <b>7-6-76</b> Well depth <b>106</b> ft.
top soil			0	3	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
gray clay			3	11	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
sand			11	17	9. Casing: Material <b>steel</b> Height <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>30.3</b> lbs./ft. Dia. <b>16</b> in. to <b>46</b> ft. depth Wall thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>7 ga.</b>
brown clay			17	21	10. Screen: Manufacturer's name <b>Doerr</b> Type <b>double-slot</b> Dia. <b>16"</b> Slot gauze <b>1/8"</b> Length <b>60"</b> Set between <b>46</b> ft. and <b>106</b> ft. Gravel pack? <b>yes</b> Size range of material <b>3/8-200</b>
sand			21	30	11. Static water level: <b>16'</b> ft. below land surface Date <b>5-18-76</b> mo./day/yr.
sand, gravel & clay streaks			30	40	12. Pumping level below land surfaces: <b>N/C</b> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.
sand & gravel			40	65	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
blue clay			65	67	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade
sand & gravel			67	78	15. Well grouted? <b>yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
brown clay			78	83	16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
sand & gravel			83	91	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>FMC Corp/Peerless</b> Model number <b>12MB-4</b> HP <b>75</b> Volts <b>460</b> Length of drop pipe <b>60'</b> ft. capacity <b>900</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
brown clay			91	105	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Clarke Well &amp; Equip. Inc.</b> 185 Business name License No. Address <b>Great Bend, KS 67530</b> Signed <b>[Signature]</b> Date <b>7-7-76</b> Authorized representative
brown clay			105	106	
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5