


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction NW 1/4 NW 1/4 SE 1/4	Section number 19	Township number T 21 S	Range number R 14 E
2. Distance and direction from nearest town or city: 3 mi N. 1/4 mi W. 1/2 mi N. of Radium, Ks.			3. Owner of well: Marvin Johnston R.R. or street: 2015 Forest City, state, zip code: Great Bend, Kansas 67530		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. 9 7/8 in. Completion date 4-18-78 Well depth 70 ft.
Top soil			0	3	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Brown clay			3	16	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other
Sand & gravel			16	45	9. Casing: Material pvc Height: Above or below 18 in. Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 1 1/2 in. to 70 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .237
Clay			45	58	10. Screen: Manufacturer's name CertainTeed Type pvc Dia. 1 1/16 Length 20 Slot 1/16 Set between 50 ft. and 70 ft. ft. and ☐ ft.
Good clean sand & gravel			58	70	Gravel pack? ☒ Size range of material 3/4 3/8
Clay			70		11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 4-18-78
					12. Pumping level below land surfaces: 15 ft. after 1 hrs. pumping 70 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 150 g.p.m.
					13. Water sample submitted: ☐ mo./day/yr. ☒ Yes ☐ No Date 4-18-78
					14. Well head completion: ☐ Pitless adapter ☐ inches above grade
					15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 15 ft.
					16. Nearest source of possible contamination: Salt water ft. 3000 Direction NANE Type disposal Well disinfected upon completion? HTH Yes ☐ No ☐
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Kansas 67530 Signed Sandy Kilgore Date 4-25-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5