

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Stafford</u>	Fraction <u>CN 1/4</u> 1/4 1/4 1/4	Section number <u>24</u>	Township number T <u>21</u> S R <u>14</u> <u>W</u>	Range number
2. Distance and direction from nearest town or city: <u>2 N 1 W</u>			3. Owner of well: <u>R.H. Ackerman</u>			
Street address of well location if in city: <u>Seward, KS</u>			R.R. or street: <u>2412 - 11</u> City, state, zip code: <u>Great Bend, KS</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>12-18-76</u> Well depth <u>143</u> ft.		
		7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
				9. Casing: Material <u>Steel</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>24</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>23</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>3/16"</u>		
5. Type and color of material				From	To	10. Screen: Manufacturer's name <u>Doerr</u>
<u>Top Soil - Clay</u>				<u>0</u>	<u>10</u>	Type <u>Steel</u> Dia. <u>16</u>
<u>Sandy Clay</u>				<u>10</u>	<u>35</u>	Slot/gauze <u>1/8</u> Length <u>70</u>
<u>Sand - Gravel</u>				<u>35</u>	<u>85</u>	Set between <u>73</u> ft. and <u>143</u> ft.
<u>Clay</u>				<u>85</u>	<u>95</u>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/8 - 3/4"</u>
<u>Sand - Gravel</u>				<u>95</u>	<u>100</u>	11. Static water level: <u>16</u> ft. below land surface Date <u>12-18-76</u>
<u>Clay</u>				<u>100</u>	<u>105</u>	12. Pumping level below land surfaces: <u>50</u> ft. after <u>4</u> hrs. pumping <u>1000</u> g.p.m. Estimated maximum yield <u>1300</u> g.p.m.
<u>Sand - Gravel</u>				<u>105</u>	<u>122</u>	13. Water sample submitted: <u>Yes</u> <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>12-18-76</u>
<u>Clay</u>				<u>122</u>	<u>123</u>	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>24</u> inches above grade
<u>Sand - Gravel</u>				<u>123</u>	<u>143</u>	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
						16. Nearest source of possible contamination: <u>NONE</u> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
						17. Pump: <u>Not installed</u> Manufacturer's name <u>Grundfos</u> Model number <u>4135</u> HP <u>60</u> Volts <u>460</u> Length of drop pipe <u>100</u> ft. capacity <u>800</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Kelly's Water Well Ser 186</u> Business name <u>R2 Great Bend, KS</u> License No. <u>1-15</u> Address <u>Kelly Price</u> Date <u>1-15</u> Signed <u>Kelly Price</u> Authorized representative
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5