


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 NE 1/4 NW 1/4	Section number 32	Township number T 21 S R 14 E	Range number 14
2. Distance and direction from nearest town or city: 5 1/2 miles Northwest of Seward, KS Street address of well location if in city:				3. Owner of well: John Neeland Box 227 City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 9 in. Completion date 6-20-78 Well depth 60 ft. Pump Set 7-18-78		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil		0	3	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 in. to 50 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 200		
Brown clay		3	18	10. Screen: Manufacturer's name Jess & Lowell Type Styrene 200 Dia. 5" Slot/gauze 1/8" Length 10 Set between 50 ft. and 60 ft. ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200		
Sandy clay & sand		18	33	11. Static water level: ☐ mo./day/yr. 23 ft. below land surface Date 6-20-78		
Sand & Gravel		33	60	12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: ☐ Pitless adapter 12 Inches above grade		
				15. Well grouted? Yes With: XX Cement ☐ Bentonite ☐ Concrete ☐ Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☐ Not installed Manufacturer's name Berkeley Pump Co. Model number 4BL-15 HP 1 Volts 230 Length of drop pipe 43 ft. capacity 15 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 7-19-78 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5