


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4	Center of 1/4 SW 1/4	Section number 34	Township number T 21 S	Range number R 14 E
2. Distance and direction from nearest town or city: 3 miles west of seward, KS Street address of well location if in city:				3. Owner of well: Marvin Johnston, JR. R.R. or street: P.O. Box 757 City, state, zip code: Great Bend, KS 67530			
4. Locate with "X" in section below: 			Sketch map:		6. Bore hole dia. 5 in. Completion date 10-20-77 Well depth 55 ft.		
5. Type and color of material			From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
Top soil			0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Brown & blue clay & sandstone			3	18	9. Casing: Material PVC Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weights 63 lbs./ft. Dia. 2 1/2 in. to 45 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .110		
Sand & clay streaks			18	40	10. Screen: Manufacturer's name Peerless Plastics Type PVC Dia. 2 1/2 " Slot gauge 1/8" Length 10' Set between 45 ft. and 55 ft. ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200		
Sand & gravel			40	55	11. Static water level: ☐ mo./day/yr. 18' 6" ft. below land surface Date 10-20-77		
					12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.		
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
					14. Well head completion: ☐ Pitless adapter 12 inches above grade		
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
					16. Nearest source of possible contamination: FIELD fr. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
					17. Pump: ☒ Not installed Manufacturer's name ☐ Model number ☐ HP ☐ Volts ☐ Length of drop pipe ☐ ft. capacity ☐ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
					(Use a second sheet if needed)		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name ☐ License No. ☐ Address Great Bend, KS 67530 Signed [Signature] Date 9-12-78 Authorized representative			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5