


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Pawnee	Fraction 1/4 1/4 CSW 1/4	Section number 26	Township number T 21 S	Range number R 15 E W
2. Distance and direction from nearest town or city: 7½ mi. East of Larned, Kansas Street address of well location if in city:			3. Owner of well: Marvin Johnston, Jr. R.R. or street: 2015 Forest City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below: N Sketch map:  S 1 Mile			6. Bore hole dia. 24 in. Completion date 2-16- Well depth 70' ft.		
			7. Cable tool ___ Rotary ___ Driven ___ Dug ___ Hollow rod ___ Jetted ___ Bored <input checked="" type="checkbox"/> Reverse rotary		
			8. Use: ___ Domestic ___ Public supply ___ Industry <input checked="" type="checkbox"/> Irrigation ___ Air conditioning ___ Stock ___ Lawn ___ Oil field water ___ Other		
			9. Casing: Material Steel Height Above or below Threaded ___ Welded <input checked="" type="checkbox"/> Surface 12 in. RMP ___ PVC ___ Weight 30.3 lbs./ft. Dia. 16 in. to 34 ft. depth Wall Thickness: inches or Dia. ___ in. to ___ ft. depth gage No. 7 ga.		
5. Type and color of material			From	To	10. Screen: Manufacturer's name Doerr
Top soil			0	2	Type Double-slot Dia. 16"
Gray clay			2	8	Slot gauze 1/8 Length 36'
Sand & soft sandstone			8	17	Set between 34 ft. and 70 ft. ft. and _____ ft.
Sand, gravel & clay streaks at 28', 35' & 58'			17	68	Gravel pack? Yes Size range of material 3/8-200
Brown clay & limestone			68	70	11. Static water level: _____ mo./day/yr. 16 ft. below land surface Date 12-31-75
					12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
					13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> Na Date _____
					14. Well head completion: Pitless adapter 12 Inches above grade
					15. Well grouted? Yes With: <input checked="" type="checkbox"/> Neat cement ___ Bentonite ___ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes ___ No <input checked="" type="checkbox"/>
					17. Pump: _____ Not installed Manufacturer's name FMC Corp./Peerless Model number 12MB-3 HP 50 Vals 460 Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ___ Submersible <input checked="" type="checkbox"/> Turbine ___ Jet ___ Reciprocating ___ Centrifugal ___ Other
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed [Signature] Date 3-4- Authorized representative		
Topography: ___ Hill ___ Slope ___ Upland ___ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5