

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>McPherson</b>	Fraction <b>SW 1/4 SE 1/4 SW 1/4</b>	Section number <b>3</b>	Township number <b>T 21 S R 2</b>	Range number <b>(NW)</b>
2. Distance and direction from nearest town or city: <b>3 North + 3/4 W of Mountridge</b>			3. Owner of well: <b>Orlo Stucky (box 14)</b> R.R. or street: <b>RR #2 Mountridge KS</b> City, state, zip code:			
4. Locate with "X" in section below:			Sketch map:		6. Bore hole dia. <b>14</b> in. Completion date <b>6/19/78</b> Well depth <b>48</b> ft.	
			7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input checked="" type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
			9. Casing: Material <b>plastic</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>13"</b> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <b>3.58</b> lbs./ft. Dia. <b>6</b> in. to <b>48</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>280</b>		10. Screen: Manufacturer's name <b>Western - Own Slot</b> Type <input type="checkbox"/> Dia. <b>6"</b> Slot/gauze <b>.046</b> Length <b>28'</b> Set between <b>22</b> ft. and <b>40</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>#1 coarse 18/14</b>	
5. Type and color of material			From	To	11. Static water level: <b>14</b> ft. below land surface Date <b>6/19/78</b>	
Loam to dark clay			0	5	12. Pumping level below land surfaces: <b>17</b> ft. after <b>2</b> hrs. pumping <b>18</b> g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield <b>25/30</b> g.p.m.	
Dark clay			5	10	13. Water sample submitted: <b>X</b> Yes <input type="checkbox"/> No Date	
" " to Brown clay			10	15	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>18</b> inches above grade	
Brown clay to sandy clay			15	20	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>12</b> ft. to <b>0</b> ft.	
SAND - MED to coarse (some clay)			20	28	16. Nearest source of possible contamination: ft. <b>140</b> Direction <b>SW</b> Type <b>Septic</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Clay - w/ limk rock ledge			28	30	17. Pump: Manufacturer's name <b>Dempster</b> Not installed Model number <b>H-50</b> HP <b>1/2</b> Volts <b>115</b> Length of drop pipe ft. capacity <b>18</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
SAND - with some clay mixed			30	39	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>PAUL'S INC. #175</b> Business name License No. Address <b>Box 26 Hession, KS</b> Signed <b>Paul Bullant</b> Date <b>7/5/78</b> Authorized representative	
SHALE - green grey			39	44		
" - red soft shale			44	48		
(Use a second sheet if needed)						
18. Elevation:		19. Remarks: <b>Good well - "cleaned up"</b> <b>FASJ"</b>			20. Water well contractor's certification:	
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5