


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>McPherson</u>	Fraction <u>SW 1/4 SW 1/4 NW 1/4</u>	Section number <u>24</u>	Township number <u>T 21 S</u>	Range number <u>R 2 W</u>
2. Distance and direction from nearest town or city: Street address of well location if in city:	<u>3 mi. N AND 1 mi. EAST OF MOUNDRIAGE, KS.</u>		3. Owner of well: <u>Lowell Koehn</u> R.R. or street: <u>305 E. Oyrst</u> City, state, zip code: <u>Moundridge KS, 67107</u>		
4. Locate with "X" in section below: Sketch map:			6. Bore hole dia. <u>8</u> in. Completion date <u>10-6-78</u> Well depth <u>47</u> ft.		
5. Type and color of material	From	To	7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
<u>Top soil</u>	<u>0</u>	<u>5</u>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<u>Hard pink clay</u>	<u>5</u>	<u>15</u>	9. Casing: Material <input type="checkbox"/> Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>72</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u>2</u> lbs./ft. Dia. <u>4</u> in. to <u>37</u> ft. depth Wall Thickness: inches or Dia. <u>4</u> in. to <u>37</u> ft. depth gage No. <u>25 in</u>		
<u>Buff clay + some fine sand</u>	<u>15</u>	<u>35</u>	10. Screen: Manufacturer's name <u>Peerless Plastics</u> Type <u>PVC</u> Dia. <u>4"</u> Slot/gauze <u>1/16</u> Length <u>10'</u> Set between <u>37</u> ft. and <u>47</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>1/4</u>		
<u>Med. Course sand + clay layers</u>	<u>35</u>	<u>40</u>	11. Static water level: <u>14</u> ft. below land surface Date <u>10-6-78</u> mo./day/yr.		
<u>Fine + med. sand</u>	<u>40</u>	<u>43</u>	12. Pumping level below land surfaces: <u>30</u> ft. after <u>1</u> hrs. pumping <u>6</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>10</u> g.p.m.		
<u>Green shale</u>	<u>43</u>	<u>47</u>	13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>		
			14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> Inches above grade		
			15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>4</u> ft. to <u>14</u> ft.		
			16. Nearest source of possible contamination: ft. <u>125</u> Direction <u>North</u> Type <u>sewer line</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			17. Pump: <u>Not installed</u> Manufacturer's name <u>METERS</u> Model number <u> </u> HP <u>3/4</u> Volts <u>230</u> Length of drop pipe <u>45</u> ft. capacity <u>12</u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>PETERSON IRRIGATION 138</u> Business name License No. Address <u>Box 150 LINDSBORG KS</u> Signed <u>Mike Peterson</u> Date <u>11-6-78</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5