

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: McPherson		NW 1/4 NE 1/4 NW 1/4	30	T 21 S	R 2 X/W
Distance and direction from nearest town or city street address of well if located within city? 3 3/4 mi west Moundridge Ks					
2 WATER WELL OWNER:		Well No. 12 (TH 1-82)			
RR#, St. Address, Box # :		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code :		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 134 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 64 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 44' ft. below land surface measured on mo/day/yr 5-4-83			
		Pump test data: Well water was 90 ft. after 6 hours pumping 513 gpm			
		Est. Yield 475 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 36 in. to bottom ft. and in. to ft.			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		Welded X			
2 PVC 4 ABS		Threaded			
Blank casing diameter 12 in. to 107 ft. Dia		5 Wrought iron 8 Concrete tile			
Casing height above land surface 36 in., weight 44 lbs./ft. Wall thickness or gauge No.		6 Asbestos-Cement 9 Other (specify below)			
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 Fiberglass			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		10 Asbestos-cement			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		11 Other (specify)			
SCREEN OR PERFORATION OPENINGS ARE:		12 None used (open hole)			
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)		9 Drilled holes			
2 Louvered shutter 4 Key punched 7 Wire wrapped 10 Other (specify)		11 None (open hole)			
SCREEN-PERFORATED INTERVALS: From 97 ft. to 107 ft. From 114 ft. to 134 ft.		12 None used (open hole)			
GRAVEL PACK INTERVALS: From 20 ft. to 134 ft. From ft. to ft.		13 None used (open hole)			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other		Grout Intervals: From 0 ft. to 20 ft. From ft. to ft. From ft. to ft.			
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well		12 Fertilizer storage 16 Other (specify below)			
2 Sewer lines 5 Cess pool 8 Sewage lagoon 13 Insecticide storage none known		17 Other (specify below)			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		18 Other (specify below)			
Direction from well? all directions		How many feet? 4 mile			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	16	Brown clay			
16	45	Gray clay			
45	64	Brown clay			
64	70	Fine to med. sand			
70	73	Brown clay			
73	80	Med. sand			
80	92	Brown clay			
92	107	Med. sand			
107	113	Gray clay			
113	134	Fine to med. sand & gravel			
134		Shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-4-83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 102 This Water Well Record was completed on (mo/day/yr) 5-17-83 under the business name of Layne Western Company, Inc. by (signature) Donalt Agnew					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

84 ck.