

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47591

1 LOCATION OF WATER WELL: County: McPherson		Fraction NW ¼ NW ¼ SW ¼ ¼		Section Number 33	Township No. T 21 S	Range Number R 2 22 ☒ W				
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ . From 20th Ave and Apache Rd go N 1/2 mile to tree row on East side of Rd.				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m						
2 WATER WELL OWNER: Ray Flickner RR#, Street Address, Box #: 2701 North Shore Circle City, State, ZIP Code : Wichita, KS 67205										
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="border-collapse: collapse; text-align: center;"> <tr> <td style="padding: 5px;">-- NW --</td> <td style="padding: 5px;">-- NE --</td> </tr> <tr> <td style="padding: 5px;">-- SW --</td> <td style="padding: 5px;">-- SE --</td> </tr> </table> E S -----1 mile-----		-- NW --	-- NE --	-- SW --	-- SE --	4 DEPTH OF COMPLETED WELL 120 ft. Depth(s) Groundwater Encountered (1) 35 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 35 ft. below land surface measured on mo/day/yr. 4/29/11 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 30 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 30 in. to 120 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☒ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No				
-- NW --	-- NE --									
-- SW --	-- SE --									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 5 in. to 60 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 2.5 lbs./ft., Wall thickness or gauge No. SDR26 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 60 ft. to 120 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 120 ft., From ft. to ft. From ft. to ft., From ft. to ft.										
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 3 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none - open field Direction from well Distance from well										
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS					
0	10	Top Soil	85	120	Medium Sand to Coarse Sand					
10	15	Fine Sand								
15	17	Clay								
17	19	Sand								
19	22	Clay								
22	35	Sandy Clay								
35	60	Clay								
60	65	Sand w/clay								
65	75	Fine to Medium Sand								
75	85	Fine Sand								
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 4/29/11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 5/4/11 under the business name of Premier Pump and Well Service, Inc. by (signature) <i>Patricia A. Hew</i>										
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .										