

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

PN-32

1 LOCATION OF WATER WELL: County: Pawnee Fraction 1/4 SW 1/4 NW 1/4 SE 1/4 Section Number 15 Township No. T 21 S Range Number R 20 E W Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here 1 1/2 North. 3/4 East of Burdett, KS 2 WATER WELL OWNER: Donald Nuckolls RR#, Street Address, Box #: PO Box 92 City, State, ZIP Code : Burdett, KS 67523 Global Positioning System (GPS) information: Latitude: Longitude: Elevation: Datum: Collection Method: Est. Accuracy:

3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W E S 4 DEPTH OF COMPLETED WELL 107 ft. Depth(s) Groundwater Encountered (1) ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 56'9" ft. below land surface measured on mo/day/yr. 10-8-13 Pump test data: Well water was 83 ft. after 2 hours pumping. 396 gpm EST. YIELD. 409 gpm. Well water was 83'6" ft. after 3 hours pumping. 409 gpm Bore Hole Diameter 40 in. to 107 ft., and in. to ft. WELL WATER TO BE USED AS: Irrigation Industrial Domestic-lawn & garden Monitoring well Was a chemical/bacteriological sample submitted to Department? No Water well disinfected? Yes No

5 TYPE OF CASING USED: PVC CASING JOINTS: Glued Casing diameter 16 in. to 107 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 18 in., Weight Sch. 40 lbs./ft., Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: Saw cut SCREEN-PERFORATED INTERVALS: From 107 ft. to 75 ft. GRAVEL PACK INTERVALS: From 107 ft. to 20 ft.

6 GROUT MATERIAL: Bentonite Grout Intervals: From 20 ft. to 0 ft. What is the nearest source of possible contamination: Oil well/gas well Direction from well Northeast Distance from well 700ft.

Table with 6 columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, LITHO. LOG (cont.) or PLUGGING INTERVALS. Rows include Clay, Sandy clay, Sand & gravel, Sandy clay, Sand & gravel.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo/day/year) 4-16-14 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 5-21-14 under the business name of Rosencrantz- Bemis Ent Inc by (signature) Jona Olets

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone: 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. I include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html.