

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: HODGEMAN NW 1/4 NW 1/4 SE 1/4 3 T 21 S R 22 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM HANSTON - 10 MILES NORTH & 3/4 MILE WEST

2 WATER WELL OWNER: PRUSHER, LARRY  
 RR#, St. Address, Box #: RT #2 -- BOX 252 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: JETMORE, KS 67854- Application Number: 17,450

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	<p>4 DEPTH OF COMPLETED WELL: 108 ELEVATION: 0</p> <p>Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.</p> <p>WELL'S STATIC WATER LEVEL 38 ft. below land surface measured on no/day/yr 05/22/01                  Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm</p> <p>Estimated Yield 850 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm</p> <p>Bore Hole Diameter 26 in. to 108 ft., and in. to 0 ft.</p> <p>WELL WATER TO BE USED AS: IRRIGATION</p> <p>Was a chemical/bacteriological sample submitted to department? No ;                  If yes, no/day/yr sample was submitted Water well disinfected? Yes</p>
--	---

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED  
 Blank casing diameter 16 in. to 108 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 21 lbs/ft. Wall thickness or gauge No. *2 inch 40*  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 100 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 108 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE - NEW SITE  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY 02 FINE SAND 36 BLUE CLAY			
40	60	37 FIN-COAR SAND 06 SMALL GRAVEL			
60	80	06 SMALL GRAVEL 36 BLUE CLAY 09 GRAVEL			
80	98	09 GRAVEL			
98	100	05 CLAY			
100	120	05 CLAY 24 THINROCLAYER 13 RED BED			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 06/06/01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/26/01 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Cook*