

# HORSE TIE CANYON NE

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

BDD

1. Location of well:		County <b>Hodgeman</b>	Fraction <b>SE 1/4 SE 1/4 NW 1/4</b>	Section number <b>I4</b>	Township number <b>T 2I</b>	Range number <b>S R 25</b>	<b>EW</b>
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: R.R. or street: City, state, zip code:			
2. Distance and direction from nearest town or city: <b>8W, ION, of Jetmore.</b>				3. Owner of well: <b>Olin Vieux</b> R.R. or street: <b>RT 2</b> City, state, zip code: <b>Jetmore, Kansas 67854</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>24</u> in. Completion date <u>9-8-76</u> Well depth <u>69</u> ft.			
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
				9. Casing: Material <u>steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>40</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7ga</u>			
Topsoil		0	2	10. Screen: Manufacturer's name <u>Doerr Meta</u> Type <u>Gravel Guard</u> Dia. <u>16</u> Slot/gauze <u>3/16</u> Length <u>20</u> Set between <u>40</u> ft. and <u>90</u> ft. Gravel pack? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>4</u> to <u>2</u>			
Clay		2	44	11. Static water level: <u>32</u> ft. below land surface Date <u>7-8-76</u>			
Sand		44	50	12. Pumping level below land surfaces: <u>51</u> ft. after <u>2</u> hrs. pumping <u>700</u> g.p.m. <u>52</u> ft. after <u>66</u> hrs. pumping <u>800</u> g.p.m. Estimated maximum yield <u>800</u> g.p.m.			
Clay		50	52	13. Water sample submitted: <u>Yes</u> <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>7-8-76</u>			
Sand		52	66	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> Inches above grade			
TR ROCK 66'				15. Well grouted? <u>no</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>    </u> ft. to <u>    </u> ft.			
<u>32</u>				16. Nearest source of possible contamination: ft. <u>1200</u> Direction <u>NW</u> Type <u>Well</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<u>34' sat thick</u>				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Western Land Roll</u> Model number <u>C76671</u> HP <u>20</u> Volts <u>480</u> Length of drop pipe <u>55</u> ft. capacity <u>650</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
<u>in Alluvium</u>				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Knoefler Bros. Drilling</u> Business name <u>Jetmore</u> License No. <u>130</u> Address <u>Jetmore</u> Signed <u>Dale Knoefler</u> Date <u>10-2-76</u> Authorized representative			
(Use a second sheet if needed)							
18. Elevation:	19. Remarks:						
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley	<u>2300</u> <u>66</u> <u>2234</u>						
	<u>TOPO</u>						

21 25 E 14  
 Sec 1/4 1/4 1/4  
 SE SE NW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5