

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

1 LOCATION OF WATER WELL: County: <u>McPherson</u> Distance and direction from nearest town or city street address of well if located within city? <u>Same</u>		Fraction <u>NE 1/4 SE 1/4 SE 1/4</u> Section Number <u>31</u>		Township Number <u>T 21 S</u> Range Number <u>R 3 E</u> ☒																																														
2 WATER WELL OWNER: RR#, St. Address, Box # : <u>Jasen Gaeddert</u> <u>19 13th Ave</u> City, State, ZIP Code : <u>Inman, KS 67546</u>		Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: <u>38.17675</u> Longitude: <u>097.68615</u> Elevation: <u> </u> Datum: <u>WGS-84</u> Data Collection Method: <u> </u>																																																
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL <u>203</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... <u>40</u> ft. below land surface measured on mo/day/yr. <u>2-17-11</u> Pump test data: Well water was..... <u>48</u> ft. after..... <u>1</u> hours pumping..... <u>35</u> gpm Est. Yield..... gpm: Well water was..... ft. after..... hours pumping..... gpm WELL WATER TO BE USED AS: 5 Public water supply ☒ Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes..... No ☒ ; If yes, mo/day/yr Sample was submitted..... Water well disinfected? Yes ☒ No.....																																																
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) ☒ PVC 4 ABS 7 Fiberglass Blank casing diameter <u>5</u> in. to <u>203</u> ft., Diameter..... in. to..... ft., Diameter..... in. to..... ft. Casing height above land surface..... <u>12</u> in., Weight <u>2.35</u> lbs./ft. Wall thickness or gauge No. <u>160 #</u> TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass ☒ PVC 9 ABS 11 Other (Specify) 2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped ☒ Saw cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From..... <u>183</u> ft. to..... <u>203</u> ft., From..... ft. to..... ft. GRAVEL PACK INTERVALS: From..... <u>23</u> ft. to..... <u>132</u> ft., From..... <u>155</u> ft. to..... <u>213</u> ft. From..... <u>132</u> ft. to..... <u>150</u> ft., From..... ft. to..... ft.																																																		
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ Bentonite 4 Other..... Grout Intervals: From..... <u>3</u> ft. to..... <u>23</u> ft., From..... <u>132</u> ft. to..... <u>137</u> ft., From..... <u>150</u> ft. to..... <u>155</u> ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide storage 16 Other (specify) 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well below 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 15 Oil well/gas well Direction from well?..... How many feet?.....																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">FROM</th> <th style="width: 10%;">TO</th> <th style="width: 80%;">LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr><td>0</td><td>9</td><td>Gr Clay</td></tr> <tr><td>9</td><td>34</td><td>Br Clay</td></tr> <tr><td>34</td><td>55</td><td>Tan F-M Sand</td></tr> <tr><td>55</td><td>74</td><td>Lt Grey F-M Sand</td></tr> <tr><td>74</td><td>90</td><td>Sandy Br Clay</td></tr> <tr><td>90</td><td>95</td><td>Lt Grey M Sand</td></tr> <tr><td>95</td><td>101</td><td>Lt Grey Clay</td></tr> <tr><td>101</td><td>131</td><td>Tan Sand + Sm Gravel</td></tr> <tr><td>131</td><td>140</td><td>Br Clay</td></tr> <tr><td>140</td><td>146</td><td>Tan M Sand</td></tr> </tbody> </table>		FROM	TO	LITHOLOGIC LOG	0	9	Gr Clay	9	34	Br Clay	34	55	Tan F-M Sand	55	74	Lt Grey F-M Sand	74	90	Sandy Br Clay	90	95	Lt Grey M Sand	95	101	Lt Grey Clay	101	131	Tan Sand + Sm Gravel	131	140	Br Clay	140	146	Tan M Sand	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;">FROM</th> <th style="width: 10%;">TO</th> <th style="width: 80%;">PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>146</td><td>162</td><td>Blue + Grey Clay</td></tr> <tr><td>162</td><td>177</td><td>Med Sand + layers Clay</td></tr> <tr><td>177</td><td>213</td><td>F-C Sand Tan - Sm layer Clay</td></tr> </tbody> </table>				FROM	TO	PLUGGING INTERVALS	146	162	Blue + Grey Clay	162	177	Med Sand + layers Clay	177	213	F-C Sand Tan - Sm layer Clay
FROM	TO	LITHOLOGIC LOG																																																
0	9	Gr Clay																																																
9	34	Br Clay																																																
34	55	Tan F-M Sand																																																
55	74	Lt Grey F-M Sand																																																
74	90	Sandy Br Clay																																																
90	95	Lt Grey M Sand																																																
95	101	Lt Grey Clay																																																
101	131	Tan Sand + Sm Gravel																																																
131	140	Br Clay																																																
140	146	Tan M Sand																																																
FROM	TO	PLUGGING INTERVALS																																																
146	162	Blue + Grey Clay																																																
162	177	Med Sand + layers Clay																																																
177	213	F-C Sand Tan - Sm layer Clay																																																
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>2-17-11</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>447</u> This Water Well Record was completed on (mo/day/year) <u>2-26-11</u> under the business name of <u>Miller Drilling</u> by (signature) <u>E Miller</u>																																																		
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																		