


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | |
|--|--|---|---|--------------------------------------|--|
| 1. Location of well: | County Rice | Fraction Center of 1/4 NW 1/4 SE 1/4 | Section number 8 | Township number T 21 S R 8 | Range number 8 |
| 2. Distance and direction from nearest town or city: 1 1/4 mile North of Sterling, KS Street address of well location if in city: | | | 3. Owner of well: Robert Kilbourne R.R. or street: Route 1 City, state, zip code: Sterling, KS 67579 | | |
| 4. Locate with "X" in section below: N W E S 1 Mile 1 Mile | | | Sketch map:  | | |
| 5. Type and color of material | | | From | To | 6. Bore hole dia. 24 in. Completion date 7-18-77 Well depth 50 ft. |
| Top soil & brown and gray clay | | | 0 | 9 | 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary |
| Sand, gravel & good gravel | | | 9 | 50 | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other |
| | | | | | 9. Casing: Material steel Height Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 30.3 lbs./ft. Dia. 16 in. to 10 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 7 ga. |
| | | | | | 10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot gauge 1/8" Length 40' Set between 10 ft. and 50 ft. ft. and <input type="checkbox"/> ft. Gravel pack? Yes Size range of material 3/8=200 |
| | | | | | 11. Static water level: <input type="checkbox"/> mo./day/yr. N/C ft. below land surface Date <input type="checkbox"/> |
| | | | | | 12. Pumping level below land surfaces: N/C <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m. |
| | | | | | 13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> |
| | | | | | 14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade |
| | | | | | 15. Well grouted? Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft. |
| | | | | | 16. Nearest source of possible contamination: FIELD ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |
| | | | | | 17. Pump: * <input type="checkbox"/> Not installed Manufacturer's name Berkeley Pump Co. Model number B3ZPL HP 25 Volts 460 Length of drop pipe 30 ft. capacity 375 g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input checked="" type="checkbox"/> Centrifugal <input type="checkbox"/> Other |
| | | | (Use a second sheet if needed) | | |
| 18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley | 19. Remarks: * This is a portable pump that is used on this well and also the well on the NE-SE 1/4 8-21-8, RC | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 9-13-77 Authorized representative | | |

T 21 S R 8 W E S 1/4 NW SE

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5