

1 LOCATION OF WATER WELL
 County: Rice Fraction NW 1/4 NW 1/4 SE 1/4 Section Number 32 Township Number T 21 S Range Number R 8 EW

Distance and direction from nearest town or city? 1 1/2 miles South and 1/2 mi. west of Sterling, KS Street address of well if located within city?

2 WATER WELL OWNER: Delvin Randolph
 RR#, St. Address, Box # : Rural Route Board of Agriculture, Division of Water Resources
 City, State, ZIP Code : Sterling, KS 67579 Application Number: Not Available

3 DEPTH OF COMPLETED WELL... 52 ft. Bore Hole Diameter. 24 in. to 52 ft., and in. to ft.
 Well Water to be used as:
 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well
 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 7 Lawn and garden only 10 Observation well
 Well's static water level 4.5 ft. below land surface measured on 5 month 15 day 1980 year
 Pump Test Data : Well water was ft. after hours pumping. gpm
 Est. Yield N/C gpm: Well water was ft. after hours pumping gpm

4 TYPE OF BLANK CASING USED:
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile Casing Joints: Glued Clamped
 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded X
 7 Fiberglass Threaded
 Blank casing dia 16 in. to 20 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 31.75 lbs./ft. Wall thickness or gauge No. 188
 TYPE OF SCREEN OR PERFORATION MATERIAL:
 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement
 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)
 9 ABS 12 None used (open hole)
 Screen or Perforation Openings Are:
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes
 7 Torch cut 10 Other (specify) Doerr Bridge Slot
 Screen-Perforation Dia 16 in. to 52 ft., Dia in. to ft., Dia in. to ft.
 Screen-Perforated Intervals: From 20 ft. to 52 ft., From ft. to ft., From ft. to ft.
 Gravel Pack Intervals: From 15 ft. to 52 ft., From ft. to ft., From ft. to ft.
 Annular Fill From 10 ft. to 15 ft., From ft. to ft., From ft. to ft.

5 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other
 Grouted Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination:
 1 Septic tank 4 Cess pool 7 Sewage lagoon 10 Fuel storage 14 Abandoned water well
 2 Sewer lines 5 Seepage pit 8 Feed yard 11 Fertilizer storage 15 Oil well/Gas well
 3 Lateral lines 6 Pit privy 9 Livestock pens 12 Insecticide storage 16 Other (specify below) FIELD
 Direction from well n/a How many feet n/a ? Water Well Disinfected? Yes No X
 Was a chemical/bacteriological sample submitted to Department? Yes X No If yes, date sample was submitted 7 month 13 day 1979 year Pump Installed? Yes X No
 If Yes: Pump Manufacturer's name Peerless Pump Co. Model No. 12MB-5 HP 100 Volts
 Depth of Pump Intake 45 ft. Pumps Capacity rated at 1000 gal./min.
 Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other

6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 5 month 15 day 1980 year
 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185
 This Water Well Record was completed on 6 month 2 day 1980 year under the business name of Clarke Well & Eq., Inc. by (signature) [Signature]

7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	1	Sandy topsoil	51	52	Brown clay
1	3	Fine sand			
3	25	Fine-Med sand & gravel w/coarse strk, scattered thin clay streaks			
25	34	Fine sand & gravel, thin yellow clay strk @ 25'			
34	51	Fine - Med. sand & gravel w/stks very fine sand and gravel, streak coarse gravel 38'-40'			

ELEVATION: Unknown

Depth(s) Groundwater Encountered 1. 4.5 ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)

INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY
T
21
R
8
EW
SEC.
32
NW 1/4
NW 1/4
SE 1/4