

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: HARVEY		SE 1/4 NW 1/4 NW 1/4	8	T 22 S	R 1 EW
Distance and direction from nearest town or city street address of well if located within city? 1 West & 1 North of Hesston					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : Don Peters		Application Number:			
City, State, ZIP Code : 204 S Roypp		Hesston KS 67062			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 43 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 13-15 ft. 2. _____ ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL 13 ft. below land surface measured on mo/day/yr 1-30-85			
		Pump test data: Well water was 40 ft. after 2 hours pumping 12 gpm			
		Est. Yield 10-12 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 11 in. to 43 ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		☒ 1 Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below) ☐ 2 Irrigation ☐ 4 Industrial ☐ 7 Lawn and garden only ☐ 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? ☒ Yes _____ No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS ☒ Glued _____ Clamped _____			
1 Steel		5 Wrought iron			
☒ 2 PVC		6 Asbestos-Cement			
3 RMP (SR)		9 Other (specify below)			
4 ABS		7 Fiberglass			
Blank casing diameter 5 in. to 18 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.					
Casing height above land surface 18 in., weight 2.37 lbs./ft. Wall thickness or gauge No. 2.14					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 ☒ PVC			
1 Steel		10 Asbestos-cement			
3 Stainless steel		8 RMP (SR)			
5 Fiberglass		11 Other (specify)			
2 Brass		9 ABS			
4 Galvanized steel		12 None used (open hole)			
6 Concrete tile		8 ☒ Saw cut factory			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 1020			
1 Continuous slot		6 Wire wrapped			
3 Mill slot		9 Drilled holes			
2 Louvered shutter		7 Torch cut			
4 Key punched		10 Other (specify)			
SCREEN-PERFORATED INTERVALS:		From 18 ft. to 28 ft., From _____ ft. to _____ ft.			
		From _____ ft. to _____ ft., From _____ ft. to _____ ft.			
GRAVEL PACK INTERVALS:		From 10 ft. to 43 ft., From _____ ft. to _____ ft.			
		From _____ ft. to _____ ft., From _____ ft. to _____ ft.			
6 GROUT MATERIAL:		3 ☒ Bentonite			
1 Neat cement		4 Other _____			
2 Cement grout					
Grout intervals: From 10 ft. to 0 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:		10 Livestock pens			
1 Septic tank		14 Abandoned water well			
4 Lateral lines		11 Fuel storage			
7 Pit privy		15 Oil well/Gas well			
2 Sewer lines		12 Fertilizer storage			
5 Cess pool		16 Other (specify below)			
8 ☒ Watertight sewer lines		13 Insecticide storage			
6 Seepage pit		9 Feedyard			
Direction from well? North		How many feet? 50'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	5	Loam			
5	10	brown clay to red brown			
10	13	red-brown clay			
13	18	sandy brown clay			
18	22	sand med-fine			
22	27	green-grey shale			
27	33	red shale			
33	43	Wellington shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ (1) constructed, ☐ (2) reconstructed, or ☐ (3) plugged under my jurisdiction and was completed on (mo/day/year) 1-30-85 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 457 This Water Well Record was completed on (mo/day/yr) 3/30/85 under the business name of United Water Well & Pump by (signature) Raul Brumhardt					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4