

Dyck Arboretum
c/o Tim Hansen
Planning Development Services
625 First National Bank Bldg.
Wichita, KS 67202

SUBJECT: TEST HOLE LISTINGS

#1. Location 850' east of west PL and 100' S of E-W hedge

0 - 5 loam =
5 - 10 hard red brown clay
10 - 21 sand - med. - course
27 - 33 green to red to grey shale

HOLE PUMPED - 4 GPM

#2. Location 425' E of W PL and 475' S of N PL

0 - 5 loam to sandy grey clay
5 - 10 grey clay to med. fine sand
10 - 18 sand - med. fine
18 - 23 green shale
23 - 25 red shale
25 - 33 grey to dark shale

HOLE PUMPED - 2 GPM

#3. Location 35' E of W PL and 110' S of N PL

0 - 5 loam to brown clay
5 - 11 brown - red clay
11 - 14 sand course
14 - 18 green
18 - 21 red shale
21 - 33 grey to dark shale

HOLE PUMPED - 4 GPM

#4. Location 40' E of W PL and 210' S of N PL

0-5 loam to brown clay
5 - 10 dark brown clay
10 - 13 sandy light brown clay
13 - 15 sand med.
15 - 20 green shale
20 - 24 red shale
24 - 30 green to grey shale
30 - 33 dark shale

NOT PUMPED

#5. Location 100' E of W PL and 70' S of E-W hedge

0 - 5 loam to brown clay
5 - 10 brown sandy clay
10 - 15 tan sandy clay
15 - 20 sand - med. fine to course
20 - 25 green shale
25 - 28 red shale
28-30 green to grey shale
30-32 dark shale

NOT PUMPED

#6.

0 - 5 loam to brown clay
5 - 11 brown clay
11 - 16 sand - med.
16 - 18 green shale

HOLE PUMPED - 4 GPM