

LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Stafford		NE ¼ NE ¼ NW ¼	13	T 22 S	R 12 E
Distance and direction from nearest town or city street address of well if located within city? 3E 3N 3/8 E OF HUDSON, KS					
WATER WELL OWNER: Landmark Drilling Co.					
RR#, St. Address, Box # : Box 183		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code : Pratt, Kansas 67124		Sieskes 1-13	Application Number:		
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		DEPTH OF COMPLETED WELL: 85' ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 25 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 19 ft. below land surface measured on mo/day/yr 29 Aug 81			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 80 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter. 10 in. to 85 ft., and in. to ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot ⑥ Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No... X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued X Clamped			
1 Steel 3 RMP (SR)		Welded			
② PVC 4 ABS		Threaded			
Blank casing diameter 5 in. to 65 ft., Dia. in. to ft., Dia. in. to ft.		Casing height above land surface. 12 in., weight lbs./ft. Wall thickness or gauge No. 214			
TYPE OF SCREEN OR PERFORATION MATERIAL:		⑦ PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		11 Other (specify)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		⑧ Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped		9 Drilled holes			
2 Louvered shutter 4 Key punched 7 Torch cut		10 Other (specify)			
SCREEN-PERFORATED INTERVALS: From. 65 ft. to 85 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From. 10 ft. to 85 ft., From ft. to ft.					
GROUT MATERIAL: ① Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From. 0 ft. to 10 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well		12 Fertilizer storage 16 Other (specify below) NONE			
2 Sewer lines 5 Cess pool 8 Sewage lagoon 13 Insecticide storage					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Sandy top soil			
2	10	Sand, very fine to fine			
10	25	Clay, gray and white			
25	35	Sand, fine			
35	60	Clay, brown and tan			
60	85	Sand, fine to coarse and fine gravel			
85	90	Clay, light gray			
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 29 Aug. 81 and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 7 Jun 82					
Under the business name of Central Well & Pump Inc. Pratt, KS by (signature) <i>[Signature]</i>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					