

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82g-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: Stafford		Fraction 1/4 1/4 CNW 1/4		Section number 19X		Township number T 22 S		Range number R 13 EW						
2. Distance and direction from nearest town or city: 3 mi. South of Seward, KS Street address of well location if in city:					3. Owner of well: Jack Williamson R.R. or street: Route 3 City, state, zip code: St. John, KS 67576									
4. Locate with "X" in section below: N 1 Mile ↑ W N NE SW SE E S ↓ 1 Mile					Sketch map:					6. Bore hole dia. <u>24</u> in. Completion date <u>6-3-76</u> Well depth <u>105</u> ft.				
5. Type and color of material					From		To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary					
									8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other					
Sandy top soil					0		5		9. Casing: Material <u>Steel</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>65</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>					
									10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot gauze <u>1/8</u> Length <u>XXX XXX</u> Set between <u>65</u> ft. and <u>XXX 105</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>					
Gray clay					5		11		11. Static water level: <u> </u> mo./day/yr. <u>11</u> ft. below land surface Date <u>5-14-76</u>					
Sandy clay, sandstone & sand streaks					11		35		12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.					
White clay, brown clay & sand streaks					35		52		13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>					
Sand, gravel & thin clay streaks					52		63		14. Well head completion: <u> </u> ☐ Pitless adapter <u>12</u> Inches above grade					
Sand, gravel & clay streaks at 95' & 97'					63		105		15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.					
									16. Nearest source of possible contamination: ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? ☐ Yes ☒ No					
									17. Pump: Manufacturer's name <u>FMC Corp./Peerless</u> Not installed Model number <u>12LB-3</u> HP <u>80</u> Volts <u> </u> Length of drop pipe <u>70</u> ft. capacity <u>900</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other					
(Use a second sheet if needed)									18. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Clarke Well & Eq., Inc.</u> 185 Business name License No. <u> </u> Address <u>Great Bend, KS</u> Signed <u>D. W. Clarke</u> Date <u>6-21</u> Authorized representative					
									19. Remarks:					
18. Elevation:					20. Water well contractor's certification:									
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.									

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5