

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction 1/4 1/4 NW 1/4	Center	Section number 20	Township number T 22 S R 13 E	Range number W				
2. Distance and direction from nearest town or city: 8 3/4 miles Northwest of St. John, KS Street address of well location if in city:				3. Owner of well: Merlin Grimes R.R. or street: 3601 22nd City, state, zip code: Great Bend, KS 67530						
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td style="width: 20px; height: 20px; text-align: center;">NW</td><td style="width: 20px; height: 20px; text-align: center;">NE</td></tr><tr><td style="width: 20px; height: 20px; text-align: center;">SW</td><td style="width: 20px; height: 20px; text-align: center;">SE</td></tr></table> E S 1 Mile				NW	NE	SW	SE	Sketch map:		
NW	NE									
SW	SE									
5. Type and color of material				From	To					
Top soil				0	3					
Gray clay				3	10					
Sandy clay & sand & lime streaks				10	42					
Sand & gravel				42	70					
Blue clay				70	78					
Sand & gravel				78	114					
Blue clay				114	115					
(Use a second sheet if needed)				6. Bore hole dia. 24 in. Completion date 4-7-78 Well depth 115 ft.						
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary						
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other						
				9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 65 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.						
				10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot gauze 1/8" Length 50' Set between 65 ft. and 115 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200						
				11. Static water level: ☐ mo./day/yr. 13 ft. below land surface Date 4-7-78						
				12. Pumping level below land surfaces: Not Checked ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.						
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐						
				14. Well head completion: ☐ Pitless adapter 12 Inches above grade						
				15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.						
16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No										
17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Co. Model number 12LB-4 HP 60 Volts 460 Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other										
18. Elevation:	19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 4-28-78 Authorized representative						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5