


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction Center 1/4 1/4 SW 1/4	Section number 28	Township number T 22 S	Range number R 13 E	
2. Distance and direction from nearest town or city: 6 miles North of St. John, KS Street address of well location if in city:				3. Owner of well: Merlin Grimes R.R. or street: 3601 22nd City, state, zip code: Great Bend, KS 67530			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. 24 in. Completion date 3-28-78 Well depth 124 ft. (Well)			
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
Top soil & sand		0	9	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
Gray clay		9	25	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 64 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.			
Fine sand		25	28	10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot gauge 1/8" Length 60' Set between 64 ft. and 124 ft. ft. and ft. Gravel pack? Yes Size range of material 3/8-200			
Brown & gray clay		28	34	11. Static water level: ☐ mo./day/yr. 30 ft. below land surface Date 3-28-78			
Fine sand & gray clay & gravel		34	45	12. Pumping level below land surfaces: Not Checked ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.			
Sand & gravel		45	124	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date			
				14. Well head completion: ☐ Pitless adapter 12 inches above grade			
				15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.			
				16. Nearest source of possible contamination: FIELD ft. Direction Type Well disinfected upon completion? ☐ Yes ☒ No			
				17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Co. Model number 121b-3 HP 80 Volts --- Length of drop pipe 70 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
		(Use a second sheet if needed)					
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 4-28-78 Authorized representative			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5