


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County <u>Stafford</u>	Township name	Fraction <u>SW/4NW/4</u>	Section number <u>34</u>	Town number <u>22</u>	Range number <u>13</u>	
Distance and direction from nearest town or city: <u>3 1/2 mi S of Hudson, Mo.</u> Street address of well location if in city:			3 Owner of well: <u>Royal Brodie</u> Address: <u>Box 2, St. John, Kansas</u>				
Locate with "X" in section below: N  S 1 Mile			Sketch map:			4 Well depth: <u>70</u> ft. Date of completion <u>5-15-75</u> Well diameter <u>8</u> in.	
2 Type and color of material			From		To		5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
							6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☒ <u>Stock well</u>
<u>Sandy top soil</u>			<u>0</u>		<u>3</u>		7 Casing: Material <u>galv.</u> Height: <u>above</u> below Threaded ☐ Welded ☒ Surface <u>18</u> in. Diam. <u>4</u> in. to <u>52</u> ft. depth Drive shoe? ☐ Yes ☐ No <u>4</u> in. to <u>52</u> ft. depth
							8 Screen: Manufacturer <u>R. & B</u> Type <u>galv.</u> Dia. <u>4</u> Slot/gauze <u>1/16</u> Length <u>18'</u> Set between <u>52</u> ft. and <u>70</u> ft. Fittings: <u>4 x 1/2 - 1/2</u> Gravel pack ☒ Yes ☐ No Size range of material <u>20-30</u>
<u>Sandy Brown clay</u>			<u>3</u>		<u>20</u>		9 Static water level: <u>19</u> ft. below land surface Date <u>5-15-75</u>
<u>Brown + white clay</u>			<u>20</u>		<u>32</u>		10 Pumping level below land surfaces: <u>NA</u> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
<u>Fine sand + sandy clay</u>			<u>32</u>		<u>44</u>		11 Water sample submitted: ☐ Yes ☒ No Date ____
<u>Sandy Brown clay</u>			<u>44</u>		<u>52</u>		12 Well head completion: ☐ Pitless adapter ☒ <u>18</u> inches above grade
<u>Sand + gravel</u>			<u>52</u>		<u>70</u>		13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ ____ Depth: From <u>0</u> ft. to <u>10</u> ft.
(use a second sheet if needed)							14 Nearest source of possible contamination: ft. <u>100</u> Direction <u>SE</u> Type <u>sewer</u> Well disinfected upon completion? ☐ Yes ☐ No
16 Remarks: elevation Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley							15 Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
							17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosenburg - Boris 134</u> Business name _____ License No. _____ Address <u>West Bend, Kansas</u> Signed <u>Royal Brodie</u> Date <u>5-15-75</u> Authorized representative