

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

13554

1 LOCATION OF WATER WELL: County: <u>Stafford</u>		Fraction <u>1/4 NE 1/4 SW 1/4 SE 1/4</u>		Section Number <u>6</u>		Township No. <u>T 22 S</u>		Range Number <u>R 14</u> ☐ E ☒ W																																																																			
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ <u>3/4 South of Radium</u>				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																							
2 WATER WELL OWNER: <u>Alan Crane</u> RR#, Street Address, Box #: <u>1191 30th Avenue</u> City, State, ZIP Code : <u>Larned, Ks. 67550</u>																																																																											
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100%; text-align: center; border-collapse: collapse;"><tr><td>W</td><td>NW</td><td>NE</td><td>E</td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td>SW</td><td>SE</td><td></td></tr></table> S -----1 mile-----		W	NW	NE	E						SW	SE		4 DEPTH OF COMPLETED WELL <u>215</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL <u>35</u> ft. below land surface measured on mo/day/yr. <u>2-21-11</u> Pump test data: Well water was <u>48</u> ft. after <u>3 1/2</u> hours pumping <u>1176</u> gpm EST. YIELD <u>1376</u> gpm. Well water was <u>54</u> ft. after <u>4</u> hours pumping <u>1376</u> gpm Bore Hole Diameter <u>30</u> in. to <u>215</u> ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																													
W	NW	NE	E																																																																								
	SW	SE																																																																									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter <u>16</u> in. to <u>215</u> ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface <u>18</u> in., Weight <u>Sch 40</u> lbs./ft., Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☒ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From <u>215</u> ft. to <u>75</u> ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From <u>215</u> ft. to <u>20</u> ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																											
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From ft. to ft., From <u>20</u> ft. to <u>0</u> ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well <u>None</u> Direction from well Distance from well																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>4</td> <td>Top soil</td> <td>138</td> <td>156.5</td> <td>Sandy tan clay/ streaks of caliche</td> </tr> <tr> <td>4</td> <td>13</td> <td>Orangish brown & gray clay</td> <td>156.5</td> <td>166</td> <td>Sand & gravel- small, tight</td> </tr> <tr> <td>13</td> <td>15</td> <td>Sandy tan & gray clay</td> <td>166</td> <td>168</td> <td>Tan clay</td> </tr> <tr> <td>15</td> <td>31</td> <td>Sand & gravel- small</td> <td>168</td> <td>182</td> <td>Sand & gravel- small tight with some broken rock</td> </tr> <tr> <td>31</td> <td>67</td> <td>Sand & gravel- clean, med, loose</td> <td></td> <td></td> <td></td> </tr> <tr> <td>67</td> <td>69</td> <td>Tan & gray clay</td> <td>182</td> <td>215</td> <td>Sand & gravel- small. tight with broken rock & few small clay streak</td> </tr> <tr> <td>69</td> <td>87</td> <td>Sand & gravel-small clay streaks</td> <td></td> <td></td> <td></td> </tr> <tr> <td>87</td> <td>100</td> <td>Tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>100</td> <td>115</td> <td>Sand & gravel- small</td> <td></td> <td></td> <td></td> </tr> <tr> <td>115</td> <td>138</td> <td>Tan clay</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	4	Top soil	138	156.5	Sandy tan clay/ streaks of caliche	4	13	Orangish brown & gray clay	156.5	166	Sand & gravel- small, tight	13	15	Sandy tan & gray clay	166	168	Tan clay	15	31	Sand & gravel- small	168	182	Sand & gravel- small tight with some broken rock	31	67	Sand & gravel- clean, med, loose				67	69	Tan & gray clay	182	215	Sand & gravel- small. tight with broken rock & few small clay streak	69	87	Sand & gravel-small clay streaks				87	100	Tan clay				100	115	Sand & gravel- small				115	138	Tan clay			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	4	Top soil	138	156.5	Sandy tan clay/ streaks of caliche																																																																						
4	13	Orangish brown & gray clay	156.5	166	Sand & gravel- small, tight																																																																						
13	15	Sandy tan & gray clay	166	168	Tan clay																																																																						
15	31	Sand & gravel- small	168	182	Sand & gravel- small tight with some broken rock																																																																						
31	67	Sand & gravel- clean, med, loose																																																																									
67	69	Tan & gray clay	182	215	Sand & gravel- small. tight with broken rock & few small clay streak																																																																						
69	87	Sand & gravel-small clay streaks																																																																									
87	100	Tan clay																																																																									
100	115	Sand & gravel- small																																																																									
115	138	Tan clay																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>2-25-12</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/year) <u>4-3-12</u> under the business name of <u>Rosencrantz- Bemis</u> by (signature) <u>[Signature]</u>																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											